

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


8-35-12W

Company- FLYNN OIL CO.
Farm- Leonard Achenback No.1

SEC. 8 T. 35 R. 12W
SW SE SE

Total Depth. 5670'
Comm. 11-13-55 Comp. 12-11-55
Shot or Treated.
Contractor.
Issued. 2-25-56

County Barber KANSAS



CASING:
8 5/8" 287' cem w/250 sx

Elevation. 11421' DF

Production. Dry

Figures indicate Bottom of Formations

clay & sand	95	Base Kansas City	4650	4654
sand & shale	185	Big lime-Oswego (Desmoines)	4664	4666
red bed	475	Cherokee	4767	4769
shale & shells	1700	Cherokee Sand	4810	4817
lime & shale	1820	Mississippi	4840	4846
lime	2400	Kinderhook Limestone	5048	5059
lime & shale	2630	Chattanooga (Woodford)	5220	5230
shale & lime	3217	Misener	5250	5254
lime	3363	Viola	5274	5300
lime & shale	3515	Simpson	5390	5408
shale	3732	Simpson Sand	5422	5424
sand	3790	Arbuckle	5623	5617
sand & shale	3885			
lime & shale	3940	Rotary Total Depth	5670	5673
lime	3985			
lime & shale	4060	DST #1 3733-37', open 1 hr., fair blow thruout, Rec. 480' salt wtr, FP 100-300#, BHP 1600#/15 min.		
shale & lime	4150			
lime & shale	4345	DST #2 4188-4203, open 1 hr, very weak blow, Rec. 90' mud, FP 0-0#, BHP 1420#/15 min.		
shale, sand & lime	4420			
shale & lime	4513	DST #3 4260-4267, open 1/2 hr. fair blow, Rec. 250' salt wtr., FP 50-150#, BHP 1690#/20 min.		
chert & lime	4570			
lime & shale	4655	DST #4 4809-4825', open 1 hr, 10 min, weak blow for 35 min., by-pass, weak blow 25 min., Rec. 60' mud, FP 30-50#, BHP 90#/50 min, H.P. 3555#/9.9# mud.		
lime	4740			
lime & shale	4780	DST #5 4842-4870', open 2 hrs., gas to surface 1 hr., Rec. 180' slightly gas cut mud, FP 70-90#, BHP 489#/30 min., H.P. 2565#/10# mud.		
lime, shale & sand	4825			
lime & shale	4847	DST #6 4872-4964', open 2 hrs., weak in fair blum, rec. 2' oil cut mud & 120' mud with specks of oil, FP 60-100#, BHP 230#/30 min., HP 2590#/9.9# mud.		
chert	4935			
lime & chert	4974			
lime	5014			
shale & lime	5163			
shale, lime & chert	5215			
shale & lime	5256			
lime & shale	5292			
lime & chert	5385			
lime & shale	5396			
shale	5422			
sand	5435			
shale & lime	5478			
lime & sand	5494			
sand & lime	5530			
sand & shale	5546			
shale & lime	5589			
lime & sand	5625			
shale & lime	5640			
lime & sand	5670			
Total Depth				

Tops:	Sample	Schlumberger
Wellington Salt		1242
Base-Salt		1767
Waubaussee		2653
Tarkio		2894
Shawnee		3126
Elgin	3732	3735
Heebner	3893	3880
Toronto	3903	3893
Base Oread	3969	3936
Missouri	4150	4152
Stalnaker	4193	4188