

State Geological Survey
WICHITA BRANCH
WELL COMPLETION REPORT AND
DRILLER'S LOG

KANSAS

15-007-20847
10-35-12W
S. 10 T. 35S R. 12W^E_W

API No. 15 — 007 — 20847
County Number

Operator
Molz Oil Company

Address
Route #2 Kiowa, Ks. 67070

Well No. #1 Lease Name Kaiser


Footage Location
990' F N L 320' F E L
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Sweetman Drilling Inc. Geologist Douglas H. McGinness

Spud Date 12-9-79 Date Completed 12-9-79 Total Depth 4827' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Lawson Oil Co.

Loc. SE NE NE
County Barber



Elev.: Gr. _____
DF _____ KB 1418

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	15"	10 3/4	40#	317'	Common	300	#3%cc 2% gel
Production	7 7/8	4 1/2		4817*	Common	175	5% Salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
		4817' - 4827'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/4	4817'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 Gallon 15% Acid	4817' - 4827'
47000 lbs. 10/20 Mesh Sand 720,000 SCF Nitrogen	

INITIAL PRODUCTION

Date of first production 3-17-80	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 26 bbls. Gas 500,000 MCF Water 80 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Panhandle Eastern	Producing interval(s) 4817' - 4827' openhole

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Molz Oil Company

Well No. #1

Lease Name Kaiser

Oil

s10 T 35SR 12W^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Limestone	4385	4760	Kansas City	4385
Shale & Limestone	4760	4790	Cherokee Shale	4760
Sand & Shale	4790	4796	Cherokee Sand	4790
Chert	4804	4827 TD	Mississippi	4804
DST #1 4804-4827 Strng Blo, GTS 27" Rec. 20' GCM IF 73-73 FF 84-63 ISIP 1405 FSIP 1647 Flowed 16330 CFG/30" Flowed 7380 CFG/60" T 127'				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

[Handwritten Signature]

Signature

Title

March 20, 1930

Date

10-32-1930