

5-35-13W

Total Depth. 5650
Comm. 3-31-55 Comp. 4-28-55
Shot or Treated.
Contractor. W. J. Coppinger
Issued. 5-28-55

County Barber

K/



CASING:
13 3/8" 310' cem w/350 sx

Elevation. 1636 D.F.

Production. Dry

Figures indicate Bottom of Formations.

red bed, shells	310
red bed, shale	785
red bed, shale, shells	1150
shale, shells	1400
shale, salt	1575
shale, lime	1620
shale, lime shells	1670
anhydrite	1705
shale, lime	3500
shale	3790
lime, shale	3815
sand, shale	3900
shale	3990
lime, shale	4190
shale	4218
lime	4250
lime, shale	4300
lime	4370
lime, shale	4610
lime	4645
lime, shale	4852
lime	4920
lime, shale	5140
lime	5168
shale, lime	5260
lime	5325
lime cherty	5355
lime cherty lime	5364
cherty lime, shale	5433
shale, sand	5466
shale,	5510
shale, sand	5575
lime, shale	5650
Total Depth	RTD

Tops:

Anhydrite	1670
LeCompton	3798
Elgin Zone	3813
Heebner	4022
Toronto	4046
Douglas Group	4104
Douglas Sand	4135
Lansing	4218
Mississippian	4840
Kinderhook lime	5142
Kinderhook shale	5167
Chattanooga shale	5199
Maquoketa	5233
Viola lime	5266

Simpson shale	5403
Simpson dolomite	5407
Simpson sand	5442
Arbuckle	5588