

1-35-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. AURORA GASOLINE CO.
Farm. Bartz-Platt No. 1

SEC. 1 T. 35 R. 13W
C NE NE

Total Depth. 4840
Comm. 3-10-57 Comp. 3-28-57
Shot or Treated.
Contractor. Barbour Drilling Co.
Issued. 8-3-57

County Barber
KANSAS



Elevation. 1439

Production. 100 BOPD

CASING:

8 5/8 @ 261' w/ 225 sx cmt.
5 1/2 @ 4840' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

surface clay & sand	110
red bed & shells	265
red bed, shale & shells	950
shale & shells	1520
anhydrite & shale	1700
lime & shale	1860
lime	2005
lime & shale	2085
lime	2255
lime & shale	3565
shale	3700
sand & sandy shale	3810
sandy shale	3875
lime	3940
lime & shale	4040
lime w/ shale streaks	4114
lime	4321
lime & shale	4380
lime	4767
sand & sandy shale	4775
lime & chert	4840
Total Depth	

TOPS:	
Elgin	3622
Heebner	3835
Toronto	3844
Douglas	3909
Brown lime	4096
Lansing	4112
Cherokec shale	4708
Cherokee sand	4756
Shaley Mississippi	4772
Mississippi chat	4795
Base Mississippi chat	4824