

**KANSAS State Geological Survey**  
**DRILLERS LOG**  
 WICHITA, BRANCH

1-35-13W

S. 1 T. 35 R. 13 <sup>N</sup>/<sub>W</sub>  
 Loc. 1980' FNL & 1980' FEL NE  
 County Barber

API No. 15 — 007 — 20,304  
 County Number

Operator  
Andover Oil Company

Address  
912 Philtower Building Tulsa, Oklahoma


Well No. #24 Lease Name BARTZ Platt

Footage Location  
1880 <sup>1980</sup> feet from (N)  line 1980 feet from (E)  line

Principal Contractor DaMac Drilling Company Geologist Bob Sandridge

Spud Date 4-2-75 Total Depth 4903' P.B.T.D. 4889'

Date Completed 4-25-75 Oil Purchaser General Energy Corporation



Locate well correctly  
 Elev.: Gr. 1435.2'  
 DF \_\_\_\_\_ KB 1439.2'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28	212'	Regular	225	3% CC
Production	7-7/8"	4-1/2"	10.50	4901'	RFC	125	1% CC

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 jet/ft		4812-23'

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Frac'd w/15,000 gal wtr frac + 39,000# 10/20 sd. Max sd concentration 5#/gal, 20 BPM, 500# avg. ISDP 150#.	

**INITIAL PRODUCTION**

Date of first production 4-28-75 Producing method (flowing, pumping, gas lift, etc.) pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>35</u> bbls.	<u>20</u> MCF		

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval (s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Andover Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
Oil

Well No. #2 Lease Name Platt

S 1 T 35 R 13 W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SEE ATTACHED				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



*Bobby Young*  
Signature

Manager Drilling & Production

Title

May 20, 1975

Date

24-131

# WELL LOG

15-007-20 304

1-35s-13W

*dup*

1975

1-35s-13w

COMPANY Sands Drilling Company

SEC. 1 T. 35S R. 13W

FARM Bartz-Platt

NO. 4

LOC. 1980 FNL 1980 FEL NE/4


TOTAL DEPTH 4903'

COUNTY Barber, Kansas

COMM. 4-2-75

COMP. 4-18-75

CONTRACTOR DaMac Drilling Company, Inc.



CASING 8 5/8" @ 213' w/225 sx.  
4 1/2" @ 4901' w/125 sx.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

212'	Shale and Red Bed
1469'	Shale
1743'	Red Bed and Shale
1804'	Lime and Shale
2116'	Shale and Lime
2260'	Lime and Shale
2460'	Lime
2647'	Lime and Shale
4350'	Lime
4838'	Mississippian and Chert
4840'	Mississippian
4863'	Mississippian and Lime
4885'	Lime
4903'	Lime
4903'	R.T.D.

