

11-35-13W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J.M. HUBER CORPORATION ET AL
Farm - Achenbach No. 1

SEC. 11 T. 35 R. 13W
C NW SW

Total Depth. 5636'

Comm. 10-15-47


Comp. 11-17-47 ✓

Shot or Treated.

Contractor. J.M. Huber Corporation

Issued. 1-24-4

County. Barber
KANSAS



Elevation. 1480 feet.

CASING:

10" 560'

Production. Dry

Figures Indicate Bottom of Formations.

clay & red beds & shells	45
red bed, shells	1100
shale & shells	1365
~~salt~~ shale & shells ✓	1500
shale & shells, lime streaks	1590
lime & shale	2340
lime	2385
lime & shale	3080
shale	3105
shale & lime streaks	3230
lime & shale	3330
lime & shale streaks	3380
shale & lime	3705
sand	3855
shale & shells	3885
shale & lime streaks	3950
lime broken	4010
broken lime & shale	4096
lime	4133
shale & lime shells	4200
lime & shale streaks	4270
lime, shale breaks	4320
lime	4425
lime broken	4495
lime	4525
lime & shale	4570
lime cherty	4600
lime & shale	4730
lime (medium)	4830
lime - shale	4841
lime - chert	4855
chat, lime & shale	4890
lime - shale breaks	4915
lime & shale	5025
lime	5050
lime & shale	5103
lime	5165
shale & lime	5290
lime	5308
cherty lime, hard	5359
lime	5420
sand, lime	5426
sand	5433
sandy shale	5440
sand & shale	5477
lime - sand	5508
shale - sand streaks	5540
shale & sand	5562
sand - lime	5599
sand	5606
shale & lime	5611
Arbuckle lime	5630
lime	5636
Total Depth.	

TCPS:

Ft. Riley	2200
base Florence	2350
Base Treford	2455
Elgin Sand	3705, fair pro. No shows.
Base Elgin Sand	3856
Toronto	3957
Douglas	4005
Douglas	4020
Kansas City	4234
Top Miss.	4841
Top Viola	5280, no por. no shows.
Top Simpson Shale	5412
Top sand	5426-33, no shows, no odor.
Top Arbuckle	5611

HDST 3707-17, open 15 min. rec. 720' slt. wtr.
HDST 4843-55, open 20 min. rec 15' mud, slightly gas cut.
HDST 5411-33 open 25 min. rec. 170' muddy slt. wtr.
BHP 1300#, Flow press, 400# thru 1/4" choke.

Ran Schlumberger.