

8-35-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WILLIAM GRUENERWALD ET AL
Farm- C. Molz No. 1

SEC. 8 T. 35 R. 14W
NW NW NW

Total Depth. 5658'
Comm. 6-18-56 Comp. 7-21-56
Shot or Treated.
Contractor. Patton Drlg. Co.
Issued. 2-2-57

County Barber



CASING:
13 3/8" 187' w/250 sx cem.

Elevation. 1491' RB

Production. Dry

Figures indicate Bottom of Formations.

river sand	20
red shale	187
shale	1110
sand shale anhydrite	1800
lime-shale	4279
lime	4653
lime-shale	4760
lime	4817
lime-shale	4822
lime cherty	4908
lime	4920
lime cherty	4927
lime	5018
lime-shale	5256
lime	5261
lime cherty	5274
lime	5374
lime cherty	5405
lime	5411
lime-shale	5458
shale sdy	5597
lime-shale	5607
lime	5662 RTD
lime	5658
Total Depth	

TOPS: Scout	
Elgin	3755
Heebner	3960
Toronto	3985
Lansing	4146
Det Mississippi	4797
Chat Mississippi	4822
Kinderhook	5124
Chat	5208
Maquoketa	5252
Viola	5276
Simpson	5428
Arbuckle	5607