


16- 35- 14 W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- CITY PRODUCTS CORPORATION
Farm- Wolgamott No. 1

SEC. 16 T. 35 R. 14W
330' N of Cent of SL, Lot #4

County Barber
KANSAS



Total Depth. 5725
Comm. 9-15-54 Comp. 10-14-54
Shot or Treated.
Contractor. W. J. Coppinger
Issued. 11-6-54

CASING:
13 3/8 @ 337' w/ 250 sx cmt.

Elevation. 1491 DE

Production. Dry

Figures Indicate Bottom of Formations.

sand & clay	90	Simpson formation	5490
red bed & sand	215	Wilcox #1 (Simpson sand)	5533
red bed & shells	340	Wilcox #2	5650
red bed, shale & shells	1055	Arbuckle	5672
red bed & shells	1215		
shale & shells	1700		
anhydrite	1727		
shale & shells	1775		
lime & shale	2325		
lime	2365		
lime & shale	2430		
shale	2505		
lime & shale	3760		
shale & sand	3865		
shale	3970		
shale & lime	4057		
shale & sand	4170		
lime & shale	4283		
lime	4445		
lime & shale	4500		
lime	4595		
cherty lime	4625		
lime	4690		
lime & shale	4790		
lime	4820		
cherty lime	4850		
lime & shale	4875		
lime	4889		
chert & lime	4915	TOPS: Sample	
chert	4945	Anhydrite	1700
cherty lime	4960	Elgin sand	3823
lime	5025	Heebner	3963
lime & shale	5070	Douglas group	4056
shale	5145	Lansing	4168
shale & lime	5460	Mississippi	4844
chert & shale	5480	Mississippi chat	4885
cherty shale	5505	Kinderhook shale	5195
shale & lime	5530	Chattanooga shale	5291
sand & shale	5565	Misener sand	5335
sandy shale	5645	Maquoketa	5341
sandy shale & lime	5685	Viola	5364
sandy shale & dolomite	5725		
Total Depth			