

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

1- 35-14W


35

Company- COPPINGER & PARKER PETROLEUM CO., INC.
Farm- Sternberger No. 1

SEC. 1 T. 35 R. 14W
NE NE SW

Total Depth. 4876
Comm. 6-29-56 Comp. 7-15-56
Shot or Treated.
Contractor. Garvey Drig Co.
Issued. 5-4-57

County Barber
KANSAS



CASING:
8 5/8" 309.02' cem w/225 sx.
5 1/2" 4876' cem w/150 sx.

Elevation. 1595 DF

Production. 6,200,000 gas

Figures indicate Bottom of Formations.

red bed	311
red bed, shale	1420
shale, shells	1620
lime, shale	1983
lime	2530
lime, shale	3390
lime	3525
shale, lime	4197
lime	4876
Total Depth	

Tops: Scout
Marmaton 4689
Mississippian 4820

Ran Schlumberger to 4877

7-24-56
Perf. 4814-15 w/4 shots sq. w/100 sx. cem.
7-28-56

Perf. 4821-25 w/6 shots gas to surface
immediately estimated 2,500,00 cfpd
sip 2250.

7-31-56
Frac: 4000# sand, 40000 gals acid gel;
Rec. load.

8- 6-56 Multipoint back pressure test;
gas gauged at rate of 6,200,000 cfpd
w/show distillate, no water.
S.I.C.P. & S.I.T.P. 1660#, O.F.P. 1540#.