


1-35-15W
CNE

SEP 29 1972

API #15-007-20,185

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas 67202

Davis Ranch "B" No. 1
C NE $\frac{1}{4}$ Sec. 1-35S-15W
Barber County, Kansas



Total Depth: 4905 ft.

Elevation: 1528 ft. K.B.

Commenced: 9-10-71

Completed: 9-23-71

as gas well

1971 Intent

4 PT 676,000 CF6PD
21 BOPD + 6 BWPD / miss

Contractor: Imperial Oil Company, Rig #2

Casing Record: Set 13-3/8" at 130 ft. with 150 sacks cement. Set 8-5/8" surface casing at 875' with 450 sacks cement. Set 4 $\frac{1}{2}$ " production casing at 4904 ft., 1 ft. off bottom, with 125 sacks pozmix.

Figures indicate bottom of formations:

Sample Log Tops:

132' ream to 17 $\frac{1}{2}$ - Sand & Clay Redbed
400' Sand & Redbed
875' Redbed and Shale
940' Shale
1720' Shale - Shells
2150' Shale & Lime
2775' Lime - Shale
4175' Shale & Lime
4905' Lime
4905' Rotary Total Depth

Elgin Sand	3745 (-2217)
Heebner	3970 (-2442)
Doug. Shale	4012 (-2484)
Lansing	4164 (-2636)
Stark	4590 (-3062)
Swope	4598 (-3070)
B/KC	4678 (-3150)
Cherokee Sh.	4798 (-3270)
Cherokee Sd.	4827 (-3299)
Miss. Ch.	4836 (-3308)
Miss. Cowley	4865 (-3337)
	4905 (-3377)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily report.

IMPERIAL OIL COMPANY

Donald J. Malone
Donald J. Malone

Subscribed and sworn to before me this 12th day of November, 1971.

My Commission Expires:
March 3, 1974

Mary J. Brown
Mary J. Brown, Notary Public