
ate Geological Survey
WICHITA BRANCH

AFFIDAVIT AND COMPLETION FORM

Z-BAR C.C. "E" #1
9- 35- 15W
ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: (Oil,) (Gas), dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR TXO Production Corp. API NO. 15-007-21,092
ADDRESS 200 W. Douglas, Ste. 300 COUNTY Barber
Wichita, KS 67202 FIELD Aetna
**CONTACT PERSON Harold R. Trapp LEASE Z-Bar Cattle Co.
PHONE 265-9441
PURCHASER Delhi WELL NO. Z-Bar Cattle Co. "E" #1
ADDRESS 2150 Fidelity Union Tower WELL LOCATION
Dallas, TX 75201 300 Ft. from North Line and
DRILLING 2310 Ft. from West Line of
CONTRACTOR Freeman, Rig #1 the 9 SEC. 35S TWP. 15W RGE.
ADDRESS 251 N. Water
Wichita, Kansas 67202
PLUGGING
CONTRACTOR N/A
ADDRESS N/A
TOTAL DEPTH 5169 PBTD N/A
SPUD DATE 2-2-81 DATE COMPLETED 10-28-81
ELEV: GR 1788 DF KB 1800
DRILLED WITH (~~CABLE~~) (ROTARY) (~~AIR~~) TOOLS



WELL PLAT
(~~Quarter~~) or (Full) Section - Please indicate.

KCC
KGS ✓

Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	12¼"	13-3/8"	32#	50'		150	
Surface		8-5/8"		1015'		400	
Production		4-1/2"	10.5#	5145'		200	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
N/A	N/A	N/A

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A

TUBING RECORD

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/1500 gals 15% HCl & 300# rock salt @ 8 BPM	5145-69'

TEST DATE: PRODUCTION FORMATION: Miss.

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity
10-28-81	flowing	N/A

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	23.4 BO bbls.	99 MCFD MCF	21 BW bbls.	N/A CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)
Sold	OH 5145-69'

** The person who can be reached by phone regarding any questions concerning this information.
A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

FIELD: Aetna

9-35-15W

Name of lowest fresh water producing stratum Unknown Depth N/A
Estimated height of cement behind pipe Circulated to Surface .

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Herington	2374	-574		
Winfield	2450	-650		
Towanda	2519	-719		
Florence	2612	-812		
Bader	2813	-1013		
Foraker	3073	-1273		
Onaga	3271	-1471		
Wabaunsee	3330	-1530		
Stotler	3473	-1673		
Howard	3567	-1767		
Topeka	3622	-1822		
LeCompton	4014	-2214		
Heebner	4254	-2454		
Toronto	4268	-2468		
Douglas Grp.	4284	-2484		
Lansing	4451	-2651		
Stark	4881	-3081		
Swope	4890	-3090		
Hus	4913	-3113		
Pawnee	5048	-3248		
Cherokee	5106	-3306		
Miss.	5144	-3344		
RTD	5169			
Ran O.H. Logs				
No DSTs.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS District Geologist FOR TXO Production Corp.

OPERATOR OF THE Z-Bar Cattle Co. LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. "E" #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 28th DAY OF October 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold R. Trapp

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10th DAY OF November 1981

PAMELA S. JOLLIFF
STATEWIDE
NOTARY PUBLIC
Harvey County, Ks.
My Appt. Expires 9/14/83

Pamela S Jolliff
NOTARY PUBLIC

MY COMMISSION EXPIRES: 9/14/83