


16-35-16W

Total Depth. 6207
Comm. 6-31-54 Comp. 9-3-54
Shot or Treated.
Contractor.
Issued. 10-23-54

County COMANCHE
KANSAS



CASING:
9 5/8 2518.49' W/100 sx Pulled 455'

Elevation. 1899

Production. Dry

Figures Indicate Bottom of Formations.

shale, shells 0 - 1404
shale 1743
anhydrite 2389
lime 3063
shale, lime 3716
lime 3947
lime, shale 4164
shale 4597
lime 5928
sand, shale 6075
lime 6207
Total Depth

Tops:
Elgin Sand 4176
Heebner 4373
Toronto 4390
Douglas 4430
Lansing K.C. 4584
Base Kansas City 5111
Marmaton 5170
Miss. 5311
Kinderhook Shale 5684
Kind. Lime 5692
Woodford 5728
Viola 5753
Simpson Shale 5927
Simp. Dolomite 5931
Simp. sand 5983
Arbuckle 6125

DST #1 4397-4433 Op. 1 hr.
rec. 360' s. wtr. 20" BHP
1578#.

DST #2 4942-5012 Op. 1 1/2 hrs.
rec. 180' gas 180' GCM 180' S.
wtr. 20" BHP 1450#

DST #3 5037-5061 Op. 1 1/2 hrs.
rec. 5037' gas 80' GCM 60' HO &
GCM 30' s.wtr. 20" BHP 1163#

DST #4 6124-6135 Op. 1 1/2 hrs.
rec. 75' Gas 15' sl. GCM 25"
BHP 122# S.I.

DST #5 6124-6140 Op. 1 hr. rec.
10' drlg. mud BHP 51#/20" S.I.

DST #6 6135-6207 Op. 1 1/2 hrs.
rec. 330' Gas 35' G & Sl. OCM
90' GCM 60' G & S. Wtr. CM
BHP 1743/30" S.I.

DST #7 (Straddle Packer)
5890-5912 Op. 1 1/2 hrs. rec.
80' Gas 100' sl. GCM BHP 0#