


IMPORTANT
Kans. Geo. Survey request
samples on this well.

2 - 35 - 16W

S. 2 T. 35 R. 16 W

Loc. SW NE NW

County Comanche

640 Acres
N

Locate well correctly

Elev.: Gr. 1803

DF 1805 KB 1808

API No. 15 — 033 — 20,161
County Number

Operator

Beren Corporation

Address

1130 Vickers KSB&T Building Wichita, Kansas 67202

Well No.

#3

Lease Name

Ballet Ranch

Footage Location

990 feet from (N) (X) line 1650 feet from (W) line

Principal Contractor

B & B Drilling, Inc.

Geologist

Eldon Schierling

Spud Date

October 15, 1974

Total Depth

5240

P.B.T.D.

Date Completed

October 27, 1974

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8-5/8		1018		350	
Production	7-7/8	4½	14#	5239	60/40 Poz	100	18% Salt

LINER RECORD**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	Jet	5164 - 90
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	5100'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% acid + 1500 gal. 7½% acid	5164 - 90
Frac with 78,000# sand + 84,000 gal Gel KCL water	5164 - 90

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
Waiting on connection	Flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas 7,600 MCF	Water -0- bbls.	Gas-oil ratio -0- CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Waiting on pipeline connection			5164 - 90		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Beren Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas	
Well No. 3	Lease Name Ballet Ranch		
S 2 T 35 R 16 E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
1) 45/45/60/60 Strong blow Gas to surface 21 min Gauged 10 min 12.7 MCF 15 min 15.7 MCF 20 min 18.5 MCF 25 min 20.7 MCF 2nd opening 10 min 40.9 MCF 20 min 35.9 MCF 30 min 34.0 MCF & stable Rec. 60' gas cut mud 1860/1813 47/65	5126	5180	Heebner 4260 Lansing 4464 Kansas City 4708 B. Kansas City 4963 Marmaton 4975 Cherokee Shale 5099 Eros. Miss. 5140 Miss. Chert 5161 Miss. Cowley 5189 L.T.D. 5238
			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Don Beauchamp, Geologist Title May 23, 1975 Date		