

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

4-35-16W

API No. 15 — 033 — 20,408
County Number

S. 4 T. 35S R. 16W

Loc. NE SW SW

County Comanche

Operator

Lee Banks

Address

200 W. Douglas #550 Wichita, Kansas 67202

Well No.

#1

Lease Name

McMoran

Footage Location

200' S. of NE SW SW
feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

D. R. Lauck Oil Co., Inc.

Geologist

Scott Banks

Spud Date

1/18/81

Total Depth

5298'


P.B.T.D.

Date Completed

1/31/81

Oil Purchaser

640 Acres



Locate well correctly

Elev.: Gr. 1815

Dr. KB 1820

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft	Setting depth	Type cement	Sacks	Type and percent additions
surface csg.	12 $\frac{1}{4}$	8 5/8	24#	416'	common	250	2% gel 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPS
Disposition of gas (vented, used on lease or sold)				Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3810 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-3206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Lee Banks		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. #1	Lease Name McMoran	
4 T 35S 16W E		

WELL LOG

Show all important facts of porosity and contents thereof, tested intervals, and all drill-stem tests, including depth interval tested, cushion used, time test open, flowing and shut-in pressures, and permeability.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.			TOP	BOTTOM	NAME	DEPTH
DST #1	4878-4912	30/45/60/60			Heebner	4315
GTS 10"		25" 68 MCF			Brown Lime	4514
15"	78 MCF	30" 68 "			Lansing	4530
20"	68 "				Swope	4903
					Hertha	4957
2nd opening					Fort Scott	
5"	39 MCF	35" 34 MCF			(Pawnee)	5128
7"	54.7 "	40" 30.8 "			Cherokee	5167
5"	51.8 "	45" 29 "			Miss.	5236
7"	48.7 "	50" 27 "			R. T. O.	5300
25	40.9 "	55" 25 "			E. L. T. D.	5298
30	37.6 "	60" 25 "				
IDP 2400# FHP 2379# IFP 106-117# FFP 149-191# ISIP 1773# FSIP 1663# Rec. 630' gassy mud cut water Chlorides 74,000						
DST #2	4956-4970	30/30/30/30				
IP	2485#	FHP 2443#				
IFP	85-74	FFP 159-149				
ISIP	1600	FSIP 1621				
Strong blow to weak blow Rec. 60' gas cut drilling mud & 90' muddy gas cut water						
T #3	5232-5260	30/45/120/90				
strong blow/GTS 60" on 2nd flow " 7.67 MCF/D 80" 8.14 MCF/D " 8.57 MCF/D 100 - 120" 16.5 MCF/D Rec. 120' water cut mud...60' mud						
P	2357	FHP 2258				
IFP	57-59	FFP 67-79				
ICIP	827	FCIP 1509				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Lee Banks Signature geologist Title 3/26/61 Date
---------------	---

4-32-1110