

KANSAS DRILLERS LOG

WICHITA BRANCH


API No. 15 — 033 ^{*} — 20275
County Number

S. 9 T. 35S R. 16 E W

Loc. C SW SW

County Comanche

640 Acres
N



Locate well correctly

Elev.: Gr. 1889

DF 1896 KB 1899

Operator McCoy Petroleum Corporation

Address One Main Place / Suite 410 Wichita KS 67202

Well No. 1 Lease Name McMoran

Footage Location 660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Sweetman Drilling Inc Geologist Bob McGinn

Spud Date 12-14-78 Total Depth 5785' P.B.T.D. 5742'

Date Completed 5-11-79 Oil Purchaser Delhi (Gas) Koch (oil)

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28 [#]	365'	common	300	2% gel 3% calcium Chlor.
Production	7 7/8	4 1/2	10.5 [#]	5781'	common	200	1/4 [#] sack cellulose

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	Jumbo Jets	5292' to 5312'

Size	Setting depth	Packer set at
2 3/8 EUE	5279'	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2-7-79 ACID 1500 gallons 15% MCA	5292 to 5312
2-8-79 FRAC 30,000 gallons Versifrac + 30,000 [#] of 20-40 sand	

INITIAL PRODUCTION

Date of first production 5-11-79 Producing method (flowing, pumping, gas lift, etc.) flow

RATE OF PRODUCTION PER 24 HOURS	Oil <u>15</u> bbls.	Gas <u>210</u> MCF	Water <u>70</u> bbls.	Gas-oil ratio <u>14,000/1</u> CFPB
---------------------------------	---------------------	--------------------	-----------------------	------------------------------------

Disposition of gas (vented, used on lease or sold) sold Producing interval (s) 5292 to 5312

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-033-20275

9-35-16W

C SW SW

ate Geological Survey
WICHITA, BRANCHWELL LOG
McMoran #1
C SW SW 9-35-16W
Comanche County, KansasName Of Operator: McCoy Petroleum Co.
816 Vickers KSB & T Bldg.
Wichita, Kansas 67202

Date Completed: January 15, 1979

FROM	TO	
0	1830	Red bed and shale
1830	5290	Lime and shale
5290	5392	Miss.
5392	5482	Chert and lime
5482	5785	Lime
5785		Total Depth

LTD 5787.3888

MC COY PETROLEUM COMPANY
816 VICKERS-KSB&T BLDG.
WICHITA, KS. 67202

6-79
#1 MC MORAN

9-35-16W
C SW SW

CONTR SWEETMAN DRILLING CTV COMANCHE

GEOL BOB MC CANN FIELD YELLOWSTONE NORTH EXT (1/2 N)

E 1899 KB CM 12/20/78 CARD ISSUED 5/26/79 P 18 BO & BWPD
F 280 MCFGPD
MISS 5292-5312

API 15-033-20,275

LOG	TOPS	DEPTH	DATUM
CHASE		2486	-587
WAB		3404	-1505
TARK		3554	-1655
HOW		3760	-1861
ELG ZN		4158	-2259
ELG SD		4220	-2321
HEEB		4382	-2483
LANS		4576	-2677
SWOPE		4980	-3081
HERT		5026	-3127
MARM		5106	-3207
PAW		5196	-3297
CHER		5238	-3339
MISS		5286	-3387
COWLEY		5356	-3457
VIOLA		5747	-3848

10-3/4" 361/300sx, 4 1/2" 5781/200sx
DST (1) 4924-5000/30-45-60-60, 250'M,
SIP 1510-1280#, FP 84-95/116-137#
DST (2) 5012-50/30-45-60-60, GTS 24",
TSTM, REC 190' GCM, SIP 1374-1123#
FP 84-73/116-95#
DST (3) 5272-5340/30-45-60-90, (2ND OP)
GTS 6", GA 14,000 CFG/60", REC 90'
GCM, (PLUGGING ACTION), SIP 1584-
1899#, FP 349-508/487-370#
MICT - CO, PF 40/5292-5312, SWB DWN &
VTG 15 MCFGPD, NAT, AC 1500, REC LD &
KO FLO 100 MCFGPD, FRAC 30,000 G
VERSA FRAC & 30,000#SD, SWB & FLO LD,
POP, SICP 1668#, P 18 BO & 82 BWPD &
FLO 280 MCFGPD, CP 325#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS