

State Geological Survey
KANSAS DRILLERS LOG
 WICHITA BRANCH

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.


15-191-20918
7-35-2W

S. 7 T. 35 R. 2 E W

Loc. SW NE SW

County Sumner

640 Acres
 N



Locate well correctly

Elev.: Gr. 1097'

DF 1100' KB 1102'

API No. 15 — 191 — 20,918
 County Number

Operator
Petroleum Resources Co.

Address
P. O. Box 631 Cushing, Okla 74023

Well No. #1 Lease Name
Fichter

Footage Location
1650 feet from XX (S) line 1650 feet from X (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist James D. Mantzke

Spud Date 7-17-79 Total Depth 4782 P.B.T.D.

Date Completed 7-30-79 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24	253	Regular	225	3% cl, 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
D&A					
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Fichter	Dry Hole
S 7 T 35 S R 2 W		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Schlumberger Tops:				
Stalnaker Sand	3130	3332		
Cottage Grove Sand	3572	3630		
Kansas City	3656	3700		
Marmaton	3906	4032		
Cherokee	4032	4340		
Miss Chat	4340	4383		
Miss Solid	4383	4629		
Kinderhook	4629	4688		
Woodford	4688	4746		
Viola	4746	4761		
Simpson Sand	4761			
TD	4779			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>R. H. Burrage</i> R. H. Burrage Signature Engineer Title 8-8-79 Date
---------------	---

1-22-50

7-35-2W
SW NE SW

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Fichter #1
SW-NE-SW Sec 7-358-2W
Sumner County Kansas

Commenced: 7-17-79

Completed: 7-30-79

OPERATOR: Petroleum Resources Co.


Depth		Formation	Remarks
From	To		
0	260	Redbed-Shale	Ran 12 jts of 28# 8 5/8" csg set @ 258' Cemented w/ 225 sks Common 2% Gel 3% CC PD @ Midnight 7-17-79
260	730	Shale	
730	970	Shale-Shells	
970	2075	Shale	
2075	2265	Shale-Lime	7-35-2W
2265	2585	Shale	
2585	2765	Shale-Lime	
2765	3105	Shale	
3105	3340	Shale-Sand	
3340	3465	Shale-Lime	
3465	3635	Lime-Shale	
3635	4310	Lime	
4310	4410	Shale	
4410	4458	Shale-Lime	
4458	4500	Lime-Shale	
4500	4750	Lime	
4750	4782	Lime-Sand	
	4782 - TD		

DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me this 31st day of July, 1979.


ELIZABETH J. EDWARDS-NOTARY PUBLIC