

pp
m

State Geological Survey
WICHITA BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

6-35-20W

S. 6 T. 35 R. 20 X
W
Loc. C E/2
County COMANCHE

API No. 15 — 033 — 20,332
County Number

Operator
Rains & Williamson Oil Co. Inc.

Address
435 Page Ct., 220 W. Douglas, Wichita, KS 67202


Well No. 1 Lease Name Tuttle 'a' 'A'

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Rains & Williamson Oil Co., Inc. Geologist Glenn Tracy

Spud Date 4-30-80 Total Depth 5611' P.B.T.D.

Date Completed 5-20-80 Oil Purchaser



SEP

Elev.: Gr. 1766

DF KB 1775

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/2"	8 5/8"	20#	680'	Portland 50/50 poz.	100 sx. 375 sx.	3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. #1 Lease Name Tuttle "A"

S 6 T 35S R 20 ^X_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 5254-5335, 30 (30) 60 (30). Rec. 40' mud. FP's 86-64, 53-53. IBHP 75, FBHP 75. Temp. 128°.			E. LOG TOPS	
			B/Lecompton	4134 (-2359)
			Heebner	4304 (-2529)
			Lansing	4506 (-2731)
			Swope	4996 (-3221)
			Hertha	5042 (-3267)
			BKC	5100 (-3325)
			Marmaton	5126 (-3351)
			Cherokee	5292 (-3517)
			Morrow Shale	5428 (-3653)
			Morr. A. Sand	5500 (-3725)
			LTD	5568 (-3793)
DST #2 - 5418-5492, 30 (45) 60 (60). Rec. 278' mud. FP's 64-64, 97-97. IBHP 1431, FBHP 1852.				
DST #3 - 5492-5520, 30 (45) 60 (60). Rec. 1440' SW, 90' Mud. FP's 211-809. FSIP 2046.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Wilson Rains

 Wilson Rains Signature

 President
Title

 6-10-80
Date