

8-35-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SINCLAIR OIL & GAS
Farm- C. H. Tuttle No. 1

SEC. 8 T. 35 R. 21W
C NW SE

Total Depth. 7600'
Comm. 7-14-61 Comp. 9-1-61
Shot or Treated.
Contractor. Barbour Drlg.
Cased. 1-13-62

County Clark
KANSAS



Elevation. 1892'

Production. 8,500,000 CFG

CASING:

30" 25' cem w/3 cu. yd. cement.
13 3/8" 617' cem w/600 sx.
9 5/8" 2886' cem w/200 sx.
4 1/2" 5695' cem w/400 sx. Figures indicate Bottom of Formations.

surface	118
red bed, shale & shells	575
red bed	617
red bed & shale	920
shale	1620
shale & lime	2055
Anhydrite & shale	2200
Anhydrite	2260
lime	2400
Anhydrite	2807
Anhydrite & dolomite	2878
Anhydrite	2887
lime	3583
shale & lime	3710
lime & shale	3904
shale & lime	4000
lime	4067
lime & shale	4176
shale	4343
lime & shale	4705
lime	6113
lime & chert	6187
lime	6210
lime & chert	6282
lime	6340
lime & shale	6444
lime	6472
lime & shale	6624
lime	7288
lime & chert	7328
lime	7350
lime & chert	7377
sand & shale	7425
shale	7450
lime	7600

Total Depth

TOPS: SCOUT

Topeka	3406
Elgin Sand	4227
Heebner	4367

Lovell Sand	4406
Toronto	4428
Lansing	4552
Marmaton	5240
Cherokee	5381
Morrow	5540
Morrow Sand	5592
Mississippi Chester	5605
St. Genevieve	5786
St. Louis	5845
Spergen	6034
Warsaw	6304
Osage	6538
Kinderhook	6836
Viola	7117
Simpson Sand	7370
Arbuckle	7480