

APR 8 1987

34

1 110002

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,757N/2 SE NE, SEC. 5, T 35 S, R 26 W/E3672 feet from S section line660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060Operator: Zinke & Trumbo, Ltd.

Name &

Address 111 West 5th, Suite 220Tulsa, OK 74103Lease Name Loyd Smith Well # 1-5County Meade204.75Well Total Depth 6300 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 1448Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Eagle Drilling, Inc. License Number 5380Address Box 8609, Wichita, KS 67208Company to plug at: Hour: 12:30 a.m. Day: 8 Month: 4 Year: 1987Plugging proposal received from Keith Hill(company name) Crown Consulting (phone) 316-624-0156were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2241'
Anhydrite 1223'1st plug at base of surface pipe plus 30' with 40 sx cement,2nd plug at 1/2 surface pipe with 40 sx cement,3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,5th plug to circulate mousehole with 10 sx cement.Plugging Proposal Received by James Kapp
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 5:30 a.m. Day: 8 Month: 4 Year: 1987ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,2nd plug at 800' with 40 sx cement,3rd plug at 40' with 10 sx cement,4th plug to circulate rathole with 15 sx cement,5th plug to circulate mousehole with 10 sx cement.Remarks: Used 60/40 Pozmix 6% gel by B.J. Wigan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-15-87INV. NO. 16548APR 13 1987
CONSERVATION DIVISION
Wichita, Kansas

Signed

James Kapp
(TECHNICIAN)FORM CP-2/3
Rev. 01-84