

KANSAS

Kans. Geol. Survey request samples on this well.

5-35-26 W

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 5 T. 35S. R. 26W. W

API No. 15 — 119-20 — 412
County Number

Loc. C SW SW

Operator CALVIN EXPLORATION, INC.

State Geological Survey
WICHITA, BRANCH

County MEADE COUNTY, KANSAS

640 Acres
N

Address 1125 SEVENTEENTH ST., SUITE 2000, DENVER, COLORADO 80202


Well No. #1-5 Lease Name EDIGER

Footage Location 660' FSL feet from (N) (S) line 660' FWL feet from (E) (W) line

Principal Contractor Search Drilling Co. Geologist Gary F. Chavez

Date Began Aug. 5, 1980 Date Completed Aug. 20, 1980 P&A Total Depth 6300' P.B.T.D. -----

Directional Deviation TD @2426' Oil and/or Gas Purchaser -----



Locate well correctly
Elev.: Gr. 2146'
DF 2154' KB 2156'

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	30"	20"		72'	Class H	250	2% CaCl
Surface	12-1/4"	8-5/8"	23#	1183'	65/35 Pozmix	475	6% gel, 1/4# D29/sk,
					Class H	225	2% CaCl 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used none Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

W 22-2E-7

Operator **CALVIN EXPLORATION, INC.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
 Well No. #1-5 Lease Name **EDIGER** DRY HOLE
 S 5 T 35S R 26W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Conductor Pipe	0	77	Heebner	4401'
Red Bed	77	1183	Marmaton	5320'
Red Bed	1183	1882	Cherokee	5493'
Lime and Shale	1882	3108	Atoka	5806'
Lime and Shale	3108	5054	Morrow	5873'
Lime and Shale	5054	6300	Chester	5960'
Rotary Total Depth	6300			
			P&A	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Signature: Gary C. Wilkins
 Title: Vice President Exploration-Production

Date: _____