

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

5 - 35 - 26W

Company- SUN OIL COMPANY
Farm- H. N. Ediger No. 1

SEC. 5 T. 35 R. 26W
C SE NW

Total Depth. 6475'

Comm. 4-11-60

Comp. 5-7-60


Shot or Treated.

Contractor. Falcon-Seaboard

Issued. 7-9-60

County Meade

KANSAS



Elevation. 2180' RB.

Production. Dry & Abnd.,

CASING:

20" @ 48' W/6yds. cem.,
8 5/8" @ 1488' W/850 sks. cem.,

Figures Indicate Bottom of Formations.

red bed	659
lime, sand, shale & Anhydrite	1500
shale & lime	1655
lime & shale	1830
lime w/thin strks shale	3490
lime & shale	4395
lime	4474
shale & lime	4512
lime & shale	4592
lime w/thin strks. shale	5800
shale & lime	5874
Morrow shale	
shale w/lime strks.	5953
Morrow sand	5964
Mississippi chester	
lime & shale	5998
shale	6030
lime w/shale strks.	6164
shale	6210
lime	6250
limey shale	6282
lime & shale	6351
lime	6405
shale	6416
sandy lime	6443
St. Genevieve Limey, sand	6475
Total Depth.	

SCOUT TOPS:

Heebneer	4426
Lansing	4593
Morrow Sand	5953
Chestnut	5969
St. Genevieve	6416

DRILL STEM TESTS:

#1. 5969-6025' rec. 15' Mud.
#2. 6383-6470' rec. 10' Mud.
#3. 5962-5979' rec. 100' Mud.