

508 East Murdock,

Wichita, Kansas

12-35-26W

Company- Wagner & Wyant Drilling
 , Farm- Theis No. 1

SEC. 12 T. 35 R. 26W
 C NE

Total Depth. 6350' 6450

Comm. 7-20-64


Comp. 8-13-64

Shot or Treated.

Contractor. Co. Tools

Issued. 11-14-64

County MEADE
 KANSAS



2190 GL

Elevation. 2201 KB

Production. D & A

CASING:

8 5/8" @ 710 w/ 300 sx:

Figures Indicate Bottom of Formations.

Redbeds Shale & Gyp	1612
Shale & Anhydrite	2332
Shale, Anhy. & dolo. Strks	2596
Lime & Shale	2967
Lime, shale & Chalk	3502
Lime & Shale	3973
Lime & Shale	4361
Lime & Shale	4697
Lime & Shale	4967
Lime & Sandy Lime	5148
Lime	5338
Lime & chert	5514
Lime	5688
Lime & Shale	5877
Lime	6112
Lime & Sandy lime	6396
Lime & Sand	6350
TOTAL DEPTH	

TOPS

Red cave	1406
Wellington	1886
Herrington	2512
Heebner	4484
Toronto	4530
Lansing	4677
Marmaton	5358
Cherokee	5539
Morrow	5583
Chester	5987
Merimer	6289

DST # 1 (Chester) 6005' - 6345' Tool Op
 6 min. fair blow IHP 3402 P.S.I. Closed
 30 min fair blow ISIP 1074 P.S.I. Open
 1 35 min fair blow IFP 299 P.S.I. Closed
 30 min. FFP 449; FSIP 1287 P.S.I. Rec.
 210' Drilling Mud. FHP 3459 P.S.I.

DST # 2 Op 5 min. Very weak blow IHP 3281 P.S.I.
 Closed 30 min very weak blow ISIP 559 P.S.I.
 Op 30 min Blow died 25 min. IFP 66 P.S.I.
 Closed 60 min FFP 181 P.S.I.
 FSIP 444 P.S.I.

Rec. 113' Drilling mud FHP 3248

electric logs run