

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


5-35-27W

Company- IMPERIAL OIL COMPANY
 Farm- Thonhoff "A" No. 1

SEC. 5 T. 35 R. 27W
 C NW SE

Total Depth. 3130'
 Comm. 3-19-63 Comp. 3-28-63
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 9-28-63

County Meade
 KANSAS



Elevation 2330' K. B.

Production. 4,450,000 CFG

CASING:

8 5/8" 1261' cem w/ 600 sx
 4 1/2" 3129' cem w/ 125 sx

Figures indicate Bottom of Formations.

shale & sand	530
shale & red bed	1235
anhydrite	1275
shale & shells	2215
shale & lime	2610
lime	2661
lime & shale	2765
lime	3130 RTD
Total Depth	

TOPS:SMP		ELECTRIC
Anhydrite	1235	1215
Winfield	2680	2680
Council Grove	3026	3025

DST# 1 3020-70 Op 45 min. Gas to surface in 4 min, gauge 1,790 MCFGPD in 5 min. 2,420 MCFGPD in 8 min., 2,580 MCFGPD in 10 min 2500 MCFGPD with spray of rotary mud in 30 min. 2,580 MCFGpd with a spray of rotary mud in 45 min. Rec. 100' gas cut mud. ICIP 947#, in 15 min. IF 462#, FF 522#, BHP 917#, in 15 min.

DST #2 3072-92 op 30 min. Rec. 4' rotary mud. IF 0#, FF 0#, BHP 0# in 15 min