


2-39W + MAP NO. (OWWO) SEC. 8-35S-27W
 STATE Kans COUNTY Meade LOC C SW NE
 OPER. Jack Grace Prod Co. FT/FR LINE
 WELL 1 FARM Judy Meyers (OWWO) FT/FR LINE
 POOL Wildcat ELEV. 2318 GR. 2330-0 DF 2333-0 KB
 CONT. Co., tools GEOL.
 CO. INT.

F.R. 10-22-62 SPUD COMP. 2-5-63
 TD. 6812 FM. St Lou PBTD. 3100

PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
CG	3049-72	14		4000A



Data Inc.

COMPLETION RECORD
 PROD. INTERVAL
 & TREATMENT
 PROD. FM. - I.P.

(3 miles W of Miss Gas)

Ga 1356 Mcfgpd (24/64" choke) SIP 840#

LOG
 RECORD

SIZE	DEPTH	SAX	SIZE	DEPTH	SAX
8 5/8"	1147				
5 1/2"	3263	125			

OPER. Jack Grace Prod Co. SEC. 8-35S-27W
 WELL 1 Judy Meyers (OWWO) ELEV. 2333 OKB C SW NE

(Old Log KB Tops)

CG 3068 - 735
 Hb 4450 -2117
 Marm 5200 -2867
 Morr sh 5950 -3617
 Morr sd 6022-66 -3689
 Chest 6116 -3783
 St Gen 6515 -4182
 OTD (St Gen) 6570 -4237

(New Log KB Tops)

Wre 2917 - 584
 CG 3045 - 712
 St Lou 6602 -4269
 LTD (St L) 6812 -4479

Old Info: (Was Apache Oil #1
 Judy Meyers Unit)

DST #1 (Morr) 6015-80, Op 1 hr
 1300' SW, IBHP 1930#/30",

IFP 219#, FFP 675#, FBHP 1792#/60",

WLT #1 (Chest) 6453-55, Op 1 hr, No Rec, 16 Mcfgpd + 1080' cc
 SW, IBHP 918#/30", IFP 444#, FFP 592#, FBHP 918#/35" OTD
 6570, Comp as D&A 6-5-62,

New Info: (10-22-62) (To CO & DD to 6900' and test St Louis)
 CO & DD 6810 TD,

DST #1 (St L) 6553-6812, Op 45", R 5' M, IBHP 1810#/20",

FBHP 1080#/20", 5 1/2" 3263/125 sx., CO GRN Log, 6/3114-17
 6/3118-21, 10/3126-31 (CG) \$ dry, No show 500A (15%) Flow 20
 BSWPH NT PB 3100 6/3049-52, 8/3068-72 (CG) \$ & Flow 1,000

MCF + spray wtr, PB 3000, pf 4/2918-20, 12/2922-28, 4/2930-42,
A/500, \$ 15 BXWPH/NT, SQ/2918-42, CO 3100 PBD, tbg w/pkr
@ 3000, A/4000 (15%) in perfs 3049-72, g 1,535 MCF (28/64" ck),
g 1,356 MCF (24/64" ck), SIP 840, CG 3049-72. 1/28/63.