


State KANSAS Field ~~KS~~
 Company Monsanto Chemical County Meade
 Farm Finch No. 1
 Sec. 11 Twp. 35 Range ~~26~~ 27

Spot CNE SW

Contractor Rine Dnlg

Remarks M.S. 6650



Comm. 12-9-56 Comp. 1-23-57

Elev. DF 2333 GL 2325 KB TD 6635 PB

Pay Cherta 6222-50

I.P. 5000 MCF Press. S.P. 1700

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 6628/300

16" 8 5/8 1556/900

<u>LOG</u>	Sample	Log
8 5/8 1556/900	Herr 2625	Heeb 4529
WOC	min 2732	Tor 4567
<u>DEC 19</u>	C.G. 3062	Lan 4713
DST 3108-20 op 1hr	Heeb 4577	Marin 5453
st Blo to rec 370 SW	Lan 4715	Cher 5638
EP 40-190 BHP 825/2	Marin 5456	Mar 6032
63635	Cher 5643	Cherta 6154
<u>JAN 9</u>	Mar 6036	<u>Stben 6076</u>
65893	Cherta 6158	
<u>JAN 9</u>		
DST 6216-30 op 1hr.		
st Blo, qts 44" TSTM		
rel 25' sliqcm FP 80		
BHP 2055/30		
DST 6230-50 op 1hr.		
qts 23" 180 MCF in 45"		
124 MCF in 60", rel 55' sliqcm FP 75-105		
BHP 2135/45		
6255		
<u>JAN 10</u>		
Back Dope & 6091-6122 rec 31'		
WOC & 6122-69 " 39'		

611566

New Doff

DST 6547-72, op/hr, rec 630'g, 250' o'gcs,
FP 180-150, BHP 290/30

RTD 6635 new log

~~5 1/2 @ 6628/300 w.o.c.T~~

JAN 23

MCT PB6596 PF 112/6222-50

run 2 3/8" T A/10000 Sum of 4,350 MCF in shu.

CP 1180, TP 975. Lat g 1,630 MCF in shu shu

20/64" ch. ~~50~~ ~~51~~

JAN 30

♀ 3PT BPT cal of 5000 MCF SIP 1700

