

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.


2-35-29W

S. 2 T. 35 R. 29 ^E/_W

Loc. C NW

County Meade

640 Acres
 N



Locate well correctly

Elev.: Gr. 2387

DF 2397 KB 2399

API No. 15 — 119 — 20,185
 County Number

Operator
Mesa Petroleum Co.

Address
Box 2009 Amarillo, Texas 79105

Well No. #1-2 Lease Name Adams

Footage Location
1320 feet from NO (S) line 1670 feet from NE (W) line

Principal Contractor Sterling Drilling Co. Geologist Gary Wilkins @ Denver

Spud Date 1/4/75 Total Depth 6098 P.B.T.D. 6048

Date Completed 3/13/75 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	997'KB	Lite Poz	490	
Production	7 7/8	4 1/2	10.5	6096'KB		250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2 JHPF	0.39"	5941-43
Size <u>2 3/8"</u>	Setting depth <u>5940</u>	Packer set at <u>None</u>	2 JHPF	0.39"	5971-78

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>1250 gal 15% HCL, 15,000 gal gelled water & 10,000 gal 15% HCL</u>	<u>5941-78</u>

INITIAL PRODUCTION

Date of first production <u>2/12/75</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil --- bbls.	Gas <u>3000</u> MCF	Water --- bbls.	Gas-oil ratio ---	CFPB
Disposition of gas (vented, used on lease or sold) <u>Vented</u>			Producing interval (s) <u>5941-43 & 5971-78</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AD 522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.


Operator: Mesa Petroleum Co., P. O. Box 2009, Amarillo, Tx
 DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas

Well No. 1-2
 Lease Name Adams

S 2 T 35 R 29 ^E_W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.
 SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Chase	2550
			Winfield	2686
			Wabaunsee	3500
			Heebner	4400
			Toronto	4427
			Lansing	4539
			Kansas City	4850
			Marmaton	5246
			Cherokee	5484
			Atoka	5772
			Morrow	5822
			Chester	5939



USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received _____
 Signature: *J. L. Farrell*
 Title: Operations Manager
 Date: 6/15/75

22-5810