

2-35-29W

KANSAS STATE GEOLOGICAL SURVEY WICHITA, BRANCH

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 119 County Number 20,218

Operator

Mesa Petroleum Company

Address

Box 2009 Amarillo, Texas

Well No.

#2-2

Lease Name

Adams

AMA. PROD.

Footage Location

1000 feet from ~~XXX~~ (S) line 1320 feet from ~~XX~~ (W) line

Principal Contractor

Rains & Williamson Oil Co.

Geologist

Dave Ward, Denver Office

Spud Date

2/26/76

Total Depth

6100'

P.B.T.D.

6008'

Date Completed


3/20/76

Oil Purchaser

Koch

S. 2 T.35 R. 29 E
Loc. 1000' FSL & 1320' FWL

County Meade

640 Acres
N

Locate well correctly

Elev.: Gr. 2326'

DF 2332' KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	23#	1447'	HOWCO Lite "H"	600 200	2% CaCl 3% CaCl
Production	7-7/8"	2-7/8"	6.5#	6060'	50-50 Poz	250	10% salt, 3/4% CFR 12-1/2# gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1-11/16" OD gun	5872-82'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gals 15% MCA & 60 balls & 500 gals Acetic Acid	5872-82'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
3/31/76		flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	20	222	0	11,100	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
vented			5872-82'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

KGS (1), Denver Office (1)
File

Operator MESA PETROLEUM CO.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 2-2	Lease Name Adams	OIL	
S <u>2</u> T <u>35</u> S <u>R 29</u> ^{NE} _W		Meade County, Kansas	
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
<u>SEE ATTACHED DRILLER'S LOG.</u>			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>S. E. Dobler</i> Signature Supervisor, Drilling & Production Title April 5, 1976 Date S. E. Dobler		

100-5000

WELL LOG

2-35-29W

COMPANY Mesa Petroleum Co.

RECEIVED

SEC. 2 T. 35S R. 29W
LOC. 1000' FSL & 1320' FWL

FARM Adams

NO. #2-2

MAR 17 1976

RIG. NO. 5

AMA. PROD.


COUNTY Meade
KANSAS

TOTAL DEPTH

COMM. 2-26-76

COMP. 3-12-76

CONTRACTOR Rains & Williamson Oil Co., Inc.



CASING

20

10

15

5/8" @ 1447' w/600 sx Halco Lite

ELEVATION

12

6

2% cc & 200 sx TYPE H, 3% cc

PRODUCTION

Oil

13

5

2-7/8" tubing @ 6100' w/200 sx, 50/50 pos, 12 1/2 Gil,
10% salt, CFR2-1%.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Red Bed	397
Red Bed	997
Surface	1260
Red Bed & Anhydrite	1447
Red Bed & Clay	1715
Red Bed & Sand	2105
Sand & Shale	2300
Shale & Shells	2417
Shale	2780
Shale & Lime	3084
Lime & Shale	3285
Dolo	3513
Lime	3655
Lime & Shale	3865
Shale	4307
Lime & Shale	4490
Shale & Lime	4837
Lime & Shale	5110
Shale & Lime	5210
Lime & Shale	5420
Shale & Lime	5520
Lime & Shale	5785
Shale & Lime	5882
Lime & Shale	6075
Shale & Lime	6100
<u>Rotary Total Depth</u>	<u>6100</u>