

8- 35- 29W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- PHILLIPS PETROLEUM CO.
Farm- Adams "H" No. 1

SEC. 8 35 R. 29W
NW NW NE

Total Depth. 6241'
Comm. 1-20-60 Comp. 3-17-60
Shot or Treated.
Contractor.
Issued. 5-7-60

County Meade

KANSAS



Elevation. 2381 DF

CASING:
16" 152' cem. w/300 sx.
9 5/8" 2014"
4 1/2" 6011' cem. w/160 sx.

Production. 2,800 MCFG,
5 B0 (grvty 40.6)

Figures Indicate Bottom of Formations.

sand, gravel, shells	185
gravel, sand, redbeds	809
shale, sand	1090
shale, sand, shells, red beds	1656
shale, sand	1762
shale, gyp, anhydrite	2010
shale, anhydrite, lime	2354
anhydrite, lime	2665
shale, lime	2892
shale, chert, lime	3132
lime	3227
lime, shale	3405
lime, chalk, shale	3575
lime, shale	4357
lime	4873
lime, shale	5069
sand, lime	5090
lime, shale	5753
lime, shale, sand stks.	5865
lime	6241
Total Depth	

TOPS: SCHLUMBERGER

Heebner	4301
Lower Kansas City	4411
Drum	4764
Base Kansas City	5139
Marmaton	5173
Cherokee	5378
Patterson Zone	5736
Chester	5837
St. Genevieve	6120

TOPS: SCOUT
Council Grove

Council Grove	2931
Wabaunsee	3413
Topeka	3895