

State Geological Survey

KANSAS WICHITA BRANCH

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-119-2000

API No. 15 — 119 — 20,239
County Number

S. 10 T. 35 R. 29 E. W.
Loc. 330' FEL & 1320' FSL
County Meade

Operator

R. Clay Underwood

Address

420 Oil & Gas Building Wichita Falls, Texas

Well No.

#F-7

Lease Name

Jessie S. Adams

Footage Location

1320 feet from (M) (S) line 330 feet from (E) (W) line

Principal Contractor

Triad Drilling Corp.

Geologist

John Nicholson

Spud Date

10/13/76

Total Depth

6413'

P.B.T.D.


6413'

Date Completed

11/5/76

Purchaser Gas

Kansas Power & Light Co.



F-7

Locate well correctly

Elev.: Gr.

2320

DF

KB

2330

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface String	7 7/8"	8 5/8"	24#	1526'	Hal-Lite 2%	c.c. 600	sx.
					Call H 3%	c.c. 150	sx.
Production String		5 1/2"	15.5#	6413'	50-50 Pozmix 12 1/2# gils. pr. sx.	400 sx.	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.50	5882' - 6222'
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	6238'	6238'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/21,000 gals. 15% acid	5882' - 6222'

INITIAL PRODUCTION

Date of first production 8/6/77		Producing method (flowing, pumping, gas lift, etc.) flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas 894 MCF	Water -0- bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 5882' - 6222'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. F #7	Lease Name Jessie S. Adams	Gas
S 10 T 35S R 39E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed	0	466	Compensated	
Red Bed and Shale	466	1133	Neutron-Formation	
Red Bed and Anhydrite	1133	1529	Density	6413'
Red Bed	1529	2195		
Shale	2195	2396	Dual Induction-	
Lime and Shale	2396	6413 TD	Laterolog	6413'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Operator Title March 11, 1977 Date
---------------	---