

Field Adams Ranch

State KANSAS County Meade

Company CARTER Oil CO

Farm Jessie S. Adams Well No. #1

Sec. 12 Twp. 35S Range 29N

fr N fr E fr S fr W

of C.S.W. NE

Contractor 6200' TEST

Remarks

Comm. 4-23-56 Comp. 6/20/56

Elev. 2350 DF 2341 T. D. 6130 P. B. 5950

Pay 5896-5913

I. P. 350 6000 R. P.

Casing Record: 13 3/8 477/550 7

20 10 3/4 5 1/2 6102/300

16 8 5/8 2319/200

| Date | Description | Notes | LOG |
|--------|---|-------|----------------------|
| APR 25 | TTD 515' | Tops | 2372 2372 |
| MAY 2 | 8 7/8 2319/200 ϕ 2680 | | 2372 |
| MAY 9 | TTD 3795 - Meade Holl 2512 | | |
| | 2407 - 18 7/8 parted @ 2253 wte 2896 | | |
| | bottom @ 2358 - PB to 2286 CB 2982 | | |
| | w 140 Ash. woc. | | Next 4366 |
| MAY 16 | ϕ cen to 2308 @ 2358 TOR | | 4405 |
| | set whipstock ϕ - | | Lang 4527 |
| | ϕ 2810 | | Hodges 5075 |
| MAY 23 | DST 4378-95 - OP | | Check. 5101 |
| | 20" rec 10' mud FP30 | | Marm 5246 |
| | BH 30/15 | | Oswego 5326 |
| | ϕ 4830 | | MOF 5905 |
| | | | 5805 |
| | | | 2341 |
| | | | 5894-5914 |
| | | | 5926 |
| | | | 3434 |
| MAY 10 | DST 5300-35 - OP 1 hr. Feblo T.O. rec 180' | | |
| | 9 in DP + 240' very shi ot gcm. FP10-100 | | |
| | BH 51510/20 HH 2810-2790 | | |
| | DST 5410-25 - OP 1 hr. w/ bl. + died | | |
| | rec 45' mud NS BP 15-30 BH 65/30 | | |
| JUN 6 | DST 5897-5920 OP 1 hr. 20" gts 6" aft | | |
| | 10" g 887 MCF aft 40' g 1,350 MCF aft 1 1/4 hrs | | |
| | hrs. flowed hr. mud oil. aft 1 hr 25 min | | |

5527
2341
-2186

2,060 MCF + hv. MIST oil rec 630' oil gr 41° @ 82°
FP 330 ~~570~~ BHP 2053/20 RTD 6126

ran sch. WOC Schl -
JUN 13 PROCT CO 6068 - 2" T CG 2978

~~5556. PRTA 6068~~ 2" T w ph Lay 4528
ran RA Lay. 7/4 48/5980-88/Hodges 5076
30/6002-07 78/6014-27 Checked. 5099

20 ran T w ph @ 5960 Mat m 5244
shutted 3 hrs rec 20 bbls oil Cheto 5492

A/1000 m. ~~shutted~~ shutted Mot 5810
3 hrs rec pt of load shutted Sd 5895-5915

dy. NS. PBTD 5950 pulled test 5946
T w ph. set pl @ 5950 - pf 102/5896-5913

ran 2" T w ph @ 5872 A/1000 m
flush w 31 bbls crude. frac/20,000

sd/20,000. flush w 210 bbls crude. - SITP 1258
flowed 147 bbls flowed ^{good} 2" line in

4 hrs. SI for TANKS have 750 bbls
load to rec SITP 300 SICPO PBTU.

5950. Flowed 132 bbls load in 4 hrs.
9/1632 MCF SITP 200#.

2 hrs Flowed 2 7/8" CK. 436 bbls load
gpa 3690 mcf TP 950 CPI 400

~~SITP 200#~~
7 hrs test flo 122 bbls load.

12 hrs test flo 2 7/8" CK 175 bbls New
oil. 39.8 gr. G 4,070 MCF. GOR

1/629:1 FTP 950 C.P. 1300
AMARILLO TOPS 2354 KB

- Winfield 2638 (-284)
- Heebner 4382 (-2028)
- Douglas 4393 (-2039)
- Lansing 4530 (-2175)
- Marmaton 5242 (-2888) SSG
- Morrow 5810 (-3456)
- "S-3" 5894 (-3540) T 21', por 15', G 350 BOPD
- Miss 5946 (-3592) NS
- TD 6130 (-3776)
- PBTD 5950