

3. 35-3W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY TEXAS CO.

SEC. 3 T. 35 R. 3W

FARM S. Hobbisiefken NO. 3

LOC. NE NW SW

TOTAL DEPTH 4777

COMM. 9-25-50


COMP. 11-2-50

SHOT OR TREATED

CONTRACTOR Stickle Drlg. Co.

ISSUED 12-2-50

COUNTY Sumner



CASING

10 3/4" 604' cem. w/500 sx.
7" 4752 cem. w/250 sx.

ELEVATION 1145 Ind.
1143 D.F.

PRODUCTION Flowing 1337 oil

FIGURES INDICATE BOTTOM OF FORMATIONS

soil, clay & sand	25	Base KC	3834
shale, sand & shells	135	Marmaton	3902
shale & shells	325	Cherokee	4051
shale, shells, & sand	430	Miss.	4323
shale & shells	595	Kinderhook	4671
shale & lime	605	Miserer	4718
lime & shale	830	Viola	4721
lime, shells & shale	1025	Simpson	4732
lime & shale	1105		
shale & lime	1670	Remarks:	
shale & shells	2000	11-8-50 Press. bomb test established pot. of 1337	
lime & shale	2235	bbls. oil, no wtr. 19/64" to 21/64" choke (19/64"	
sand & shale	2365	choke ofr 15 hr. averaged 15.45 bbls. oil per	
lime & shale	2540	hr; 21/64" choke ofr 3 hrs. averaged 18.90 bbls.	
lime sdy & shale	2660	oil per hr). 2-7/8" tubing, back press. on sep-	
lime	2710	arator 25#, tubing press. 220#, casing press.,	
shale & lime	2820	420#.	
lime & shale strk	2915		
shale & lime	3130		
shale & sand & shells	3226		
sand & shale	3306		
sand	3343		
lime	3370		
lime & shale	3496		
shale	3552		
shale & lime shells	3582		
sand & shale	3630		
shale	3640	chert	4345
lime	3812	cherty lime	4385
lime & shale	3857	lime & chert	4462
lime	3996	lime	4688
lime & shale	4035	shale	4720
lime	4074	lime	4777
lime & shale	4118	Total Depth	
lime brkn	4170		
shale, lime brkn	4212	Tops:	
lime & shale	4255	Stalnaker	3134
lime	4315	Layton	3587
lime & shale	4318	Kansas City	3634
sand	4323		