


4-35-3W

Company - TEXAS COMPANY
 Farm - N. J. Peters No. 2

SEC. 4 T. 35 R. 3W
 NE SE SE

Total Depth. 4770
 Comm. 1-18-51 Comp. 3-12-51
 Shot or Treated.
 Contractor. stickle Drilling Co.
 Issued. 6-23-51

County. Sumner
 KANSAS



CASING:
 10 3/4" 581' cem w/450 sx
 7" 4747' cem w/500 sx

Elevation. 1116 DF
 1118 (2nd)

Production. Bomb Potential
 5826 bbls oil.

Figures Indicate Bottom of Formations.
 ential of 5826 BO, no water,
 in 24 hrs., flowed 19 BOPH
 for 17 hrs through 5/16"
 choke. BHP 1760#, dropped
 to 1618#. csg press. 240#,
 tbg press. 550#.

sand & shale 75
 sand, shab, red bed 220
 shale & shells 325
 shale, shells, salt 578
 lime, shells 582
 lime, shale & salt 650
 lime & shale 1355
 lime, sand & shale 1445
 shale, shells & sand 1475
 shale & lime 1625
 shale & lime shells 1790
 shale & shells 1950
 lime & shale 2045
 shale & lime broken 2185
 shale, lime & sand 2330
 shale & lime 2350
 lime broken 2410
 lime broken & shale 2505
 shale & lime broken 2605
 shale & lime 3114
 sand & shale 3295
 sand 3327
 lime, shale 3345
 shale & sand 3409
 lime & shale 3511
 shale, lime & broken
 sand 3563
 sand & shale 3624
 lime 3643
 shale brkn, sand, lime 3670
 lime K.C. 3766
 lime, broken 3806
 lime broken, shale 3827
 lime broken 3871
 lime, shale 4059
 shale, broken lime 4102
 shale 4158
 shale & lime 4229
 shale, broken lime 4379
 shale, lime, sand 4300
 lime, chert, Miss. 4354
 lime 4393
 lime & chert 4441
 lime 4479
 lime & shale 4499
 lime 4667

lime & shale 4688
 shale sandy 4708
 lime 4744
 lime, sand 4756
 sand 4770
 Total Depth
 Tops:
 Kansas City 3617
 Mississippi 4307
 Kinderhook 4645
 Misener 4702
 Viola 4707
 Simpson 4722
 Simpson sand 4748

3-22-51 Pressure bomb
 test established pot-