


Company - TEXAS COMPANY
Farm - N. J. Peters No. 3

SEC. 4 T. 35 R. 3W
SW SE SE

Total Depth. 4822 PB 4811
Comm. 3-29-51 Comp. 5-7-51
Shot or Treated.
Contractor. Stickle Drilling Co.
Issued. 6-23-51

County. Sumner
KANSAS



CASING:
10 3/4" 605' cem w/450 sx
7" 4816' cem w/500 sx

Elevation. 1126 DF
1128 RB (2nd)

Production Bomb Potential
2176 bbls oil.

Figures Indicate Bottom of Formations.

clay & sand	90
shale & shells	725
shale & lime	1255
lime sandy, shale	1355
shale & lime	1625
shale, lime shells	1795
shale, lime	2070
lime, shale sandy	2215
shale, lime	3011
shale, lime shells	3121
sand, shale	3331
sand	3357
lime, shale	3400
shale, broken lime	3479
shale, lime	3536
shale, lime shells	3582
shale	3618
sand	3645
lime	3972
lime, shale	4006
lime	4042
lime, shale	4132
shale	4170
lime, shale	4235
shale sandy & lime	4275
lime & shale	4314
shale & sand	4316
chat	4338
lime	4373
lime & chert	4417
lime	4655
shale, lime	4735
lime	4748
sand	4822

Total depth
Plugged back to 4811

Tops:
Stalnaker 3127
Layton 3598
Kansas City 3638
Marmaton 3912
Cherokee 4063
Mississippi 4318
Kinderhook 4662
Wisener 4719
Viola 4733
Simpson 4748
Simpson Sand 4788

5-11-51 Flowed on State
Test 22.16 BOPH, no wtr
for 17 hrs through 3/8"
choke. Static BHP 1700#,
tbg press. 470#. Flowing
press. 1275#, dropped to 300#.
Pressure bomb potential
2176 BOPD