


9-35-3W
 County, Sumner

Total Depth. 4801 KB
 Comm. 3-17-51 Comp. 5-3-51
 Shot or Treated. Acidized
 Contractor. Barnett Drlg. Co.
 Issued. 7-7-51

KANSAS



CASING:

8 5/8" 605 cem w/400 sxs.
 5 1/2" 4782 cem w/500 sxs.

Elevation. 1124 DF
 1125 (rod)
 Production. 2036 BOPD

Figures Indicate Bottom of Formations.

shale, red bed	25	closed 20 min., rec. 100'	
red bed	47	very slightly oil & gas	
sand	85	cut mud, BHP 1065#	
red bed, shells	140	DST 4782-90, open 1 hr.,	
shale, blue	325	gas in 11 min., shut in	
shale, shells	335	15 min., rec. 30' muddy	
shale, blue sticky	405	wtr. & 650 clean oil.	
shale, blue	470	BHP 1575#	
shale, shells	602		
lime	605	Ran Schlumberger	
lime, shale	870	Cored 4790-91. Perf. 4783-	
shale, lime	1255	91 w/14 sh., swbg. mud, oil	
lime	1280	& wtr. Acidized w/1000 gals.	
lime, shale	1635	flowed 195 BO in 12 hrs.	
shale	2070	thru 1/2" choke.	
lime, shale	2810	Cored 4791-94, rec. 3'	
shale, lime	3235	dolomitic sand.	
sand, shale, shells	3320	Cored 4794-98, rec. 3'	
shale, lime	3485	sandy dolomite.	
shale	3592	DD 4801, ran tubing with	
sand	3647	packer set @ 4761	
lime	3770	Flowed 13 BO in tanks in	
lime, shale	3825	2 hrs., loaded up with wtr.	
lime	3870	Acidized w/2000 gals.	
lime, shale	3985	Flowed load oil & 350 BO	
lime	4110	with trace acid wtr. 12 hrs.	
shale, lime	4150	Killed well, pulled tubing,	
lime	4200	set Lane Wells plug 4778.	
shale, lime	4265	Perf. 4768-77 w/24 bullets	
lime	4305	& 40 Kone sh. Acidized	
shale	4350	w/2000 gals., MP 600#, used	
lime	4400	27 bbls. load oil. Drld.	
lime, chert	4460	plug, ran tubing, set	
lime	4690	packer @ 4752. Flowed 33 BOPH,	
lime, shale	4745	3 hrs. on 3/4" choke.	
shale	4760		
lime	4787		
sand, Simpson dolomite	4790		
sand, dolomite	4791		
dolomite, sandy	4793		
dolomite, slightly			
sandy	4795	Mississippian	4349
dolomite, sandy	4796	Kinderhook	4695
dolomite, very sandy	4798	Viola	4758
dolomite, sandy	4801	Simpson	4769

TOPS KB:
 Kansas City 3647

DST 3686-3705 open 1 hr., 30
 min., fair blow 20 min.,