


9-35-3W

Company- MAGNOLIA PETRO. CO.
 Farm- F. A. Hudson No. 3

SEC. 9 T. 35 R. 3W
 NE SW NE

Total Depth. 4818 KB
 Comm. 6-27-51 Comp. 7-27-51
 Shot or Treated.
 Contractor. Barnett Drlg., Inc.
 Issued. 11-24-51

County Sumner
 KANSAS



CASING:

8 5/8" 611' cem w/425 sxs.
 5 1/2" 4818' cem w/500 sxs.

Elevation. 1126 DE
 1128 (and)
 Production. 1722 BOPD

Figures indicate Bottom of Formations.

surface clay, sand	40
shale, shells	611
shale, lime	1085
shale, shells	2365
shale, lime	2450
shale, shells	2555
shale, lime	2700
shale, shells	2815
shale, lime	3185
lime, shale	3320
lime, shale	4350
lime, shale, chat	4380
chert, lime	4389
cherty lime, shale	4410
lime	4428
lime, chert	4475
lime	4738
lime, shale	4755
lime	4775
Cored to 4818	
lime	4776
lime, brn w/slight	
odor & stain	4784
lime	4786
lime w/odor & light show	
oil	4787
lime w/stain & odor	4790
lime	4792
dolomite, sandy	
saturated w/oil	4793
sand w/light sat.	
& staining	4803
dolomite, sandy,	
saturated w/light	
show oil	4811
sand, saturated w/light	
oil	4818 KB
Total depth	

Tops:
 Kansas City 3669
 Mississippian 4354
 Kinderhook 4693
 Viola 4769
 Simpson 4776

DST 4356-80, open 1 hr., 15
 min., strong blow, gas in
 8 mins., rec. 180' very
 slightly oil & heavily gas
 cut mud, no wtr., BHP 1700#
 DST 4790-4818, open 20 min.,
 gas in 6 min., flowed oil in
 13 min., BHP 1590#
 Perf. 4780-86 w/24 cone shots.
 Perf. 4795-4810 w/75 shots.
 Perf. 4810-16 w/36 shots
 Perf. 4815-18 w/15 shots.