

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

10-35-3W

Company- THE TEXAS CO.

Farm- F. A. Hudson

No. 3

SEC. 10

T. 35

R. 3W

SW NW NW

Total Depth. 4807 PB 4804

Comm. 5-14-51

Comp. 6-17-51


Shot or Treated.

Contractor. Stickle Drlg. Co.

Issued. 11-24-51

County Sumner

KANSAS



CASING:

10 3/4" 599' cem w/450 sxs.

7" 4806-1/2' w/500 sxs. cem.

Elevation. 1125 DE

Production. Pot. 6250 bbls.

Figures Indicate Bottom of Formations.

surface clay, sand 30
 sand 65
 shale, shells 600
 lime 660
 shale, lime 1110
 lime 1270
 shale, lime 1375
 shale, shells 1600
 gray shale 1790
 shale, shells 2000
 shale 2575
 shale, lime 2775
 shale, shells 2885
 lime, shale 3015
 shale 3128
 sandy lime 3182
 sand 3262
 sand, shale 3340
 shale 3480
 lime shale rough 3537
 lime, shale 3560
 sand 3595
 shale, lime 3614
 sand 3634
 lime 3722
 sandy lime 3749
 lime 4064
 shale 4102
 lime 4134
 lime, shale 4189
 lime 4235
 lime, shale 4310
 shale 4327
 lime, chert 4352
 lime 4394
 lime, chert 4442
 lime 4689
 shale 4702
 shale, lime 4713
 shale 4733
 lime 4764
 sand 4807
 Total depth PB 4804

Tops:

Stalnaker 3108
 Layton 3573
 Kansas City 3629
 Base K. C. 3823
 Marmaton 3894
 Cherokee 4043
 Mississippi 4328
 Kinderhook 4682
 Misener 4729
 Viola 4742
 Simpson 4752
 Simpson sand 4788