

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


10-35-3W

Company- THE TEXAS CO.
Farm- F. A. Hudson No. 4

SEC. 10 T. 35 R. 3W
NW SW NW

Total Depth. 4812
Comm. 11-20-51 Comp. 1-17-52
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 2-16-52

County Sumner
KANSAS



CASING:

10 3/4" 602' cem. w/425 sx
7" 4811' cem. w/500 sx

Elevation. 1123 DE
1125 (sand)

Production. 42.42 BO NW 8 hrs.

Figures Indicate Bottom of Formations.

shale & sand	100
shale & shells	175
salt, shale & shells	603
lime & shale	647
shale & shells	830
shale & lime	1855
shale & lime shells	2050
shale & lime	3162
sand & shale	3360
sandy shale & lime	3480
shale & lime	3576
sandy shale & lime	3655
lime	3683
lime & shale	3788
lime	3821
shale & lime	4345
lime & chert	4373
cherty lime	4378
lime	4703
lime & shale	4760
lime	4766
sand	4812
Total Depth	

Tops:	
Stalnaker	3114
Layton	3584
Kansas City	3643
Base-Kansas City	3837
Mississippian	4345
Kinderhook	4700
Misencr	4754
Viola	4764
Simpson	4773
Simpson Sand	4803