

16-35-3W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **CHARLES W. OLIPHANT**

SEC. 16 T. 35 R. 3W
 LOC. C LOT 4 SW/4

FARM **Enderud** NO. 1

TOTAL DEPTH **4859**
 COMM. **6-6-66** COMP. **11-30-66**
 SHOT OR TREATED
 CONTRACTOR **Corbett Crlg.**
 ISSUED **1-21-67**

COUNTY **Sumner**
 KANSAS



CASING

20	10	
15	8 5/8"	@ 250' w/200 sx
12	6	
13	5 1/2"	@ 4857' w/260 sx

ELEVATION **1140' KB**

PRODUCTION **PMP 14 BO &**
27 BWPD
(KC 3734-40) &
(SIMP 4814-17)

FIGURES INDICATE BOTTOM OF FORMATIONS

8-5/8 @ 250 W/200 sks. - circ.
 5-1/2 @ 4857 W/260 sks. .

1158 DF
 1130 GL

Production P. 14 BOPD
 27 BWPD
 K. C. & Simpson

FORMATION

Red Bed	70
Shale & Shells	253
Shale & Lm. streaks	530
Salt, an hydrite, sh.	670
Shale	690
Anhydrite	720
Shale	735
Lime, an hyd. sh. streaks	905
Shale	940
Lime & shale	1120
Lime	1200
Lime & shale	2330
Shale	2410
Lime	2600
Shale	2675
Shale & Lime	2710
Lime	2750
Lime & Shale	3280
Lime	3430
Shale	3630
Sand	3730
Lime	3760
Shale	3815
Lime & Shale	4350
Chat	4440
Lime	4665

Shale 4735
 Lime 4754
 Shale 4758
 Sand 4859 TD

Tops:

Layton	3678
Kansas City	3732
Mississippi	4338
Kinderhook	4666
Viola	4735
Simpson	4758
Total Depth	4859

DST #1 3726-3757
 40' O&GCM
 100' O&GCMF
 40' GCSM
 1500# ISIP

DST #2 4385-4426
 505' HO&GCM
 45' SGCM
 90' GCSW
 1664 #ISIP

DST #3 4791-4808
 120' O&GCM
 30' Foggy MCO
 90' Oil
 1826# ISIP

DST #4 4813-4852
 1890' HO & GCMF
 930' HGCSW
 1738# ISIP

Completed in K. C. 3734-3740
 "Simpson" 4796-4818