

11-228W/Map No. K-84 O W W O  
 OPER COLORADO OIL CO. - Wichita, Ks.



S-T-R 3-35S-30W

SPOT App SW NE

CO MEADE (Ks)

ELEV 2560 KB

(KB Log)

WELL #1 FOX "A"

R. \_\_\_\_\_  
 FIELD Adams Ranch (Multi Pay)

P. Flo 410 BOPD-NW (Gr 37.1°) - St L 6280-6312

Win	2711	-	151
UFR	2772	-	212
LFR	2855	-	295
CG	3024	-	464
Tor	4396	-	1836
LKc	4526	-	1966
Mar	5203	-	2643
Cher	5389	-	2829
Mrw	5768	-	3208
Mrw sd	5793	-	3233
Mrw sd	5847	-	3287
Mrw sd	5889	-	3329
Ches	5910	-	3350
Ste G	6126	-	3566
St L	6200	-	3640
LTD	NA		
RTD	6237	-	3677
DDTD	6330	-	3770

OLD INFO: (Was Republic Nat. Gas #1 Fox)

Spud 5-31-57, 10" @609 w/600 sx.

DST #1 (CG) 3090-3117, Op 1 hr, GTS/5", Ga 2,800,000 Cfgpd /5", Ga 2,862,000 Cfgpd/58" w/sll spray SW, R 70' SW, No ISIP, FP's 600-690#, FSIP 885#/30"

DST #2 (Tor) 4410-25, Op 1 hr, GTS/1½", OCM to surf/5½", Ga 3,480,000 Cfgpd/5", Ga 5,100,000 Cfgpd/20", R 180' oil (Gr 45 deg) & 10' SW, No ISIP, FP's 1430-1390#, FSIP 1560#/20"

DST #3 (LKc) 5077-91, Op 1 hr, R 560' SGCMSW, No ISIP, FP's 90-355#, FSIP 1725#/20"

DST #4 (Mar) 5204-24, Op 1 hr, GTS/6", Stab @66,000 Cfgpd, R 900' Oil & 600' SW, No ISIP, FP's 105-295#, FSIP 700#/20"

DST #5 (Mar) 5363-73 (Str Pkr), Op 1 hr, R 20' SO&GCM, No SIP, FP's 35-35#, FSIP 390#/20"

Con't

Data Inc

DST #6 (Mrw sd) 5803-11, Op 1 hr, GTS/2", Stab @947,000 Cfgpd/30", R 1 qt dist, No ISIP, FP's 120-140#, FSIP 2000#/30"

DST #7 (Mrw sd) 5850-65, Op 1 hr, R 20' M, No ISIP, FP's 380-495#, FSIP 1675#/30"

DST #8 (Mrw sd) 5893-5908, Op 1 hr, GTS/2", Ga 2,072,000 Cfgpd/5", Ga 2,468,000 Cfgpd/30" w/spray dist, No ISIP, FP's 615-615#, FSIP 1975#/30", RTD 6237, Ran Log, 4½" @5981 w/490 sx.

MICT, CO 5916, Pf 28/5889-96, 16/5793-97 (Mrw), Ga 2,123,000 Cfgpd-NW/2½ hrs, nat, Frac 18,000# sd x 18,000 GW, 500 MA, Ga 13,700,000 Cfgpd/4 hrs, Retr BP @5753, Pf 24/4402-08 (Tor), Ga 3,287,000 Cfgpd/30" - nat, 500 MA, Flo oil, SW & Gas/NT, Flo 30 BO & 27 BSW & 500,000 Cfgpd/24 hrs thru 1/4" choke, FTP 840#, FCP 1115#, SIFP 1200# & SICP 1210#/101 hrs; Pull retr BP @5753, Ran tbg w/pkr

15 for Dual prod, Flo 30 BOPD & 27 BWPD & 500,000 Cfgpd & 1/4" choke, FTP 840#, FCP 1115#, Tor 4402-08 (new pay), 14 hr BD 13,714,000 Cfgpd, SIP 1643#, Mrw 5793-5896 (QA) Comp Jan 15, 1953

Con't

(KB Sp1)

Herr	2580	-	20
CG	3018		
Tor	4406		
LKc	4518		
Hodges	5020	-	2460
Ckrbrd	5082	-	2522
Mar	5203		
Mrw	5788		
Mrw sd	5802		
RTD	6237		

MISCELL DATA  
 GEOL \_\_\_\_\_ ELEV \_\_\_\_\_ SPUD DATE 5-31-57  
 FTG \_\_\_\_\_ DRLG COMP \_\_\_\_\_  
 SUPPT \_\_\_\_\_ FR by DATA 11-8-65  
 CSG 10" @609 w/600 sx. 4½" @5981 w/490 sx. COMP by " 11-18-65

