

COMPANY: UNITED PRODUCING CO.  
 FARM: A. W. Adams No. 1


SEC. 2 T. 35 R. 30W  
 C SW/4

2-35-30W

Total Depth: 6240'  
 Conn: 8-15-58 Comp. 9-15-58  
 Shot or Treated.  
 Contractor: R. W. Rine Drilling Co.  
 Issued. 2-7-59

County Meade

KANSAS



Elevation. 2491' RB

Production. Dry

Casing

13 3/8" 521' cem w/500 sx.  
 8 5/8" 2593' cem w/500 sx.

Figures indicate Bottom of Formations.

surface, sand & clay	400
clay, shells & red bed	529
red bed	1180
shale & shells	1317
red bed, shale & shells	1635
red bed	1760
shale & gyp	1870
gyp & chalk	1916
Anhydrite & shale	2095
Anhydrite	2462
Anhydrite & lime	2593
lime	3010
lime & shale	3142
lime	3657
lime & shale	4090
shale	4370
lime	4442
lime & shale	4688
lime	4747
lime & shale	4821
lime & chert	4870
lime	5108
lime & chert	5136
lime	5525
shale & lime	5586
lime, shale & sand	5652
lime & shale	5769
shale & sand	5824
sand, shale & lime	5857
lime	5880
shale & lime	6011
lime	6100
lime & shale	6129
lime	6184
lime & shale	6230
lime	6235
lime	6240

Total Depth

TOPS: SCOUT	
Council Grove	2914
Lansing	4478
Marmaton	5156
Nov Pay Zn.	5267
Cherokee	5384
Morrow	5735
Morrow Sand	5852
Chester	5870
St. Geneiveve	6127