

KANSAS

6-35-30 W  
WICHITA BRANCH

**WELL COMPLETION REPORT AND DRILLER'S LOG**

S. 6 T. 35 R. 30 <sup>KX</sup><sub>W</sub>

API No. 15 — 119 — 20,431  
County Number


Loc. C NE NE

County Meade

Operator  
B & B Farm Industries, Inc.

640 Acres  
N

Address  
Box 638; Spearman, Texas 79081



Well No. 2 Lease Name Eddy

Footage Location  
660 feet from (N) ~~XX~~ line 660 feet from (E) ~~XX~~ line

Locate well correctly  
Elev.: Gr. 2442'

Principal Contractor Sage Drilling Co. Geologist Don Huber

Spud Date 9/18/80 Date Completed 10/5/80 Total Depth 6220 P.B.T.D. 4510'

Directional Deviation None Oil and/or Gas Purchaser Oil - UPG

DF KB 2453'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	24	1457	HLC	500	2% CaCl <sub>2</sub>
					H	200	3% CaCl <sub>2</sub>
Production	7-7/8"	4-1/2"	9.5	4510	Pozmix	150	18% salt 10#/sx Gilsonite 3/4 of 1% CFR-2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			1	Sand notch	4321
<b>TUBING RECORD</b>			1	1/2" jet	4318-4319
Size 2-3/8" EUE	Setting depth 4334	Packer set at None	1	1/2" jet	4327-4334

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
750 gal. 15% MCA acid	4318-4334'

**INITIAL PRODUCTION**

Date of first production Feb. 10, 1981	Producing method (flowing, pumping, gas lift, etc.) Pump
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls. Gas - MCF Water 130 bbls. Gas-oil ratio - CFPB
Disposition of gas (vented, used on lease or sold) Used on lease	Producing interval (s) 4318-4334'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator B & B Farm Industries, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

Well No. 2 Lease Name Eddy

S 6 T 35S R 30 ~~XXX~~  
W

**WELL LOG**  
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>Ran Welox DIGL and CDL/N logs from 6220' TD.</p> <p>No Cores</p> <p>No DST</p>				

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_

Signature: *R. Maginloth*

Title: President - Higginbottom Engineering

Date: 3/27/81

9-32-30 m