

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

10-35-30W

Company- THOMAS & BREWER
Farm- Adams "E"

No. 1

SEC. 10 T. 35 R. 30W
C/SW NE

Total Depth. 6075'

Comm. 8-1-59

Comp. 8-27-59


Shot or Treated.

Contractor. Bennett & Roberts Drlg. Co.

Issued. 4-30-60

County Meade

KANSAS



Elevation. 2443

Production. 10,000,000 CFG

CASING:

8 5/8" 1200' cem. w/600 SX.

5 1/2" 5920' cem. w/150 SX.

Figures indicate Bottom of Formations.

surface sand & clay	70
sand & sandy blue clay	380
sand & clay	580
blue shale & clay	650
red bed & shale	940
red bed & sand	1187
anhydrite	1215
red bed	1480
red bed & sand streaks	1620
shale & shells	1740
shale & lime	3305
chalky lime & shale	3782
lime & shale	4600
lime	4970
lime & shale	5085
lime	5641
lime & shale	5710
lime	5769
lime & shale	5770
lime	5957
lime & shale	6070RTD
lime & shale	6075
Total Depth	

TOPS: SCOUT

Council Grove.	2995
Toronto	4300
Lansing	4410
Morrow	5718
Morrow Sand	5746
Chester	5856
St. Genevieve	6068