

8-49W

Map No.

84

WILDCAT

OPER HORIZON OIL & GAS CO

SPEARMAN, TEX

WELL #1-5 ADAMS 'B'

R ZENITH DRLG. CORP., INC.

(GEOL) - ADAMS RANCH FIELD/2 MI W/ST L OIL

I.P. D&A

API #15-119-20,004

SPD 5-16-67 8-5/8 1360/650 SX BILL ATKINSON - GEOL

DST #1 (MRW) 5632-5766, OP 90", GTS/80", TSTM, R 120' GC
Ø M, ISIP 1029#/45", FP 66-82#, FSIP 1046#/45"DST #2 (ST L 'B') 6180-6205, OP 90", R 120' FREE O + 270'
SMCO + 20' HDM, SLI O & GC, NW, ISIP 2036#/30", FP
50-133#, FSIP 1939#/90"DST #3 (ST L 'C') 6245-81, OP 20", NO REC, ISIP 49#/20"
FP 32-32#, FSIP 49#/20"

RTD 6320 LOG 4½" 3610/250 SX

PF 19/6194-6223 (ST L 'B' ZN) 2000 A, PF 19/6154-84

(ST L) 2000 A, PF 17/6120-44 (ST L) 2000 A, SD FRAC
50,000#SD + 91,000 G GEL A, § LD, R 859 B OUT OF 2170 B
§ LD, R LD, FU 500'FLU (NBD) § 6-7 BFPH(90%W)

P 90 BFPD (4%O), CAST IRON PLUG @6076', PF 13/5993-6012

(CHEST), TBG PKR @5919', § DRY, 2000A(15%) W/BALL SEALERS,
2100#, TP 1800#, SI 48 HRS, § 48 BW W/TR OIL

D&A 8-7-67

COMPLETED 8-9-67

MEADE

5-35S-30W

C SW NE

HORIZON OIL & GAS CO

#1-5 ADAMS 'B'

S-T-R 5-35S-30W

SPOT C SW NE

CO MEADE, KS

ELEV 2454 KB

KB LOG TOPS

WREF 2826 - 372

C GR 2881 - 427

TOR 4249 -1795

LAN 4364 -1910

KC 4646 -2192

MAR 5091 -2637

CHER 5294 -2840

KEETING 5446 -2992

MRW SH 5640 -3186

CHEST 5756 -3302

B/" 5990 -3536

ST G 6039 -3585

ST L 6127 -3673

ST L 'B' ZN

6181 -3727

ST L 'C' ZN

6231 -3777

ST L 'D' ZN

6282 -3828

LTD 6313 -3859

KB SPL TOPS:

HB 4213

TOR 4256-1802

LAN 4362-1908

RTD 6320

MISCEL DATA

GEOL BILL ATKINSON

FTG

SUPPT

CSG

8 5/8" 1360/650 SX, 4½" 3610/250 SX

ELEV 2443 GR

SPUD DATE 5-16-67

DRLG COMP 8-7-67

FR by DATA 5-17-67

COMP by " 5-10-67