
15-175-22016 6-35s-31w



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration Inc.**

9400 N. Broadway Ste. 400 Oklahoma City
Ok. 73114

ATTN: Ed Greaves

6/35/31

Deborah #1

Start Date: 2005.12.27 @ 16:00:01
End Date: 2005.12.28 @ 03:31:58
Job Ticket #: 22911 DST #: 1

RECEIVED
APR 17 2006
KCC WICHITA

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

Raydon Exploration Inc. Deborah #1 6/35/31 DST # 1 Morrow 2005.12.27

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22911 **DST#: 1**

Test Start: 2005.12.27 @ 16:00:01

GENERAL INFORMATION:

Formation: **Morrow**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 19:16:35
Time Test Ended: 03:31:58

Test Type: Conventional Bottom Hole
Tester: Harley Davidson
Unit No: 33

Interval: 5915.00 ft (KB) To 6010.00 ft (KB) (TVD)
Total Depth: 6010.00 ft (KB) (TVD)
Hole Diameter: 7.78 inches Hole Condition: Fair


Reference Elevations: 2723.00 ft (KB)
2711.00 ft (CF)
KB to GR/CF: 12.00 ft

Serial #: 6751 **Inside**

Press@RunDepth: 47.25 psig @ 5981.00 ft (KB)
Start Date: 2005.12.27 End Date: 2005.12.28
Start Time: 16:00:02 End Time: 03:31:58

Capacity: 7000.00 psig
Last Calib.: 1899.12.30
Time On Btm: 2005.12.27 @ 19:11:10
Time Off Btm: 2005.12.27 @ 23:46:59

TEST COMMENT: IF- Weak blow , 1" into bucket.
ISI- No blow back.
FF- No blow .
FSI- No blow back.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2871.17	118.00	Initial Hydro-static
6	30.02	117.51	Open To Flow (1)
35	38.84	119.00	Shut-In(1)
95	144.74	120.64	End Shut-In(1)
96	35.42	120.60	Open To Flow (2)
152	47.25	122.15	Shut-In(2)
274	119.92	124.36	End Shut-In(2)
276	2812.71	128.51	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
120.00	100% mud.	0.59

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22911 DST#: 1

Test Start: 2005.12.27 @ 16:00:01

Tool Information

Drill Pipe:	Length:	5600.00 ft	Diameter:	3.80 inches	Volume:	78.55 bbl	
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	
Drill Collar:	Length:	310.00 ft	Diameter:	2.25 inches	Volume:	1.52 bbl	
					Total Volume:	80.07 bbl	

Drill Pipe Above KB:	22.00 ft
Depth to Top Packer:	5915.00 ft
Depth to Bottom Packer:	ft
Interval between Packers:	95.00 ft
Tool Length:	122.00 ft
Number of Packers:	2 Diameter: 6.75 inches

Tool Weight:	1800.00 lb
Weight set on Packer:	25000.00 lb
Weight to Pull Loose:	90000.00 lb
Tool Chased	0.00 ft
String Weight: Initial	88000.00 lb
Final	88000.00 lb

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			5889.00		
Shut In Tool	5.00			5894.00		
Hydraulic tool	5.00			5899.00		
Jars	5.00			5904.00		
Safety Joint	2.00			5906.00		
Packer	5.00			5911.00	27.00	Bottom Of Top Packer
Packer	4.00			5915.00		
Stubb	1.00			5916.00		
Perforations	1.00			5917.00		
Change Over Sub	1.00			5918.00		
Drill Pipe	62.00			5980.00		
Change Over Sub	1.00			5981.00		
Recorder	0.00	6751	Inside	5981.00		
Perforations	25.00			6006.00		
Recorder	0.00	6724	Outside	6006.00		
Bullnose	4.00			6010.00	95.00	Bottom Packers & Anchor
Total Tool Length:	**122.00**					

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22911 **DST#: 1**

Test Start: 2005.12.27 @ 16:00:01

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	52.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	7.97 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	4000.00 ppm				
Filter Cake:	inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
120.00	100% mud.	0.590


Total Length: 120.00 ft Total Volume: 0.590 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:

Laboratory Name: Laboratory Location:

Recovery Comments:


Pressure vs. Time
6751 Pressure
6751 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(1)
End Shut-In(2)
Open To Flow(1)
Shut-In(1)
Open To Flow(2)
Shut-In(2)
Pressure
Temperature
3000
2500
2000
1500
1000
500
0
130
120
110
100
90
80
70
60
50
40
6PM
9PM
28 Wed
3AM
27 Tue Dec 2005
Time (Hours)



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration Inc.**

9400 N. Broadway Ste. 400 Oklahoma City
Ok. 73114

ATTN: Ed Greaves

6/35/31

Deborah #1

Start Date: 2005.12.29 @ 11:00:26
End Date: 2005.12.29 @ 21:41:13
Job Ticket #: 22912 DST #: 2

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC.

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22912 **DST#: 2**

Test Start: 2005.12.29 @ 11:00:26

GENERAL INFORMATION:

Formation: **Lowwer Morrow**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 14:24:49
Time Test Ended: 21:41:13

Test Type: Conventional Bottom Hole
Tester: Harley Davidson
Unit No: 33

Interval: 6097.00 ft (KB) To 6140.00 ft (KB) (TVD)
Total Depth: 6140.00 ft (KB) (TVD)
Hole Diameter: 7.78 inches Hole Condition: Fair


Reference Elevations: 2723.00 ft (KB)
2711.00 ft (CF)
KB to GR/CF: 12.00 ft

Serial #: 6751 **Inside**

Press@RunDepth: 19.15 psig @ 6130.50 ft (KB)
Start Date: 2005.12.29 End Date: 2005.12.29
Start Time: 11:00:27 End Time: 21:41:14

Capacity: 7000.00 psig
Last Calib.: 1899.12.30
Time On Btm: 2005.12.29 @ 14:22:14
Time Off Btm: 2005.12.29 @ 18:52:40

TEST COMMENT: IF- Weak building blow , 8" into buket.
ISI- No blow back.
FF- Weak building blow , 3" into bucket.
FSI- No blow back.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	3026.62	117.83	Initial Hydro-static
3	14.98	117.83	Open To Flow (1)
29	16.22	121.34	Shut-In(1)
88	129.22	124.84	End Shut-In(1)
88	12.34	124.79	Open To Flow (2)
148	19.15	127.51	Shut-In(2)
267	256.98	130.69	End Shut-In(2)
271	2960.76	130.97	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
0.00	1000 GIP	0.00
30.00	10% gas, 90% Mud.	0.15

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration Inc.

Deborah #1

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

6/35/31

Job Ticket: 22912 **DST#: 2**

ATTN: Ed Greaves

Test Start: 2005.12.29 @ 11:00:26

Tool Information

Drill Pipe:	Length:	5780.00 ft	Diameter:	3.80 inches	Volume:	81.08 bbl	Tool Weight:		1800.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:		25000.00 lb
Drill Collar:	Length:	310.00 ft	Diameter:	2.25 inches	Volume:	1.52 bbl	Weight to Pull Loose:		100000.0 lb
					Total Volume:	82.60 bbl	Tool Chased		0.00 ft
Drill Pipe Above KB:		20.00 ft					String Weight:	Initial	85000.00 lb
Depth to Top Packer:		6097.00 ft						Final	88000.00 lb
Depth to Bottom Packer:		ft							
Interval between Packers:		42.50 ft							
Tool Length:		69.50 ft							
Number of Packers:		2	Diameter:	6.75 inches					

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			6071.00		
Shut In Tool	5.00			6076.00		
Hydraulic tool	5.00			6081.00		
Jars	5.00			6086.00		
Safety Joint	2.00			6088.00		
Packer	5.00			6093.00	27.00	Bottom Of Top Packer
Packer	4.00			6097.00		
Stubb	1.00			6098.00		
Perforations	1.00			6099.00		
Change Over Sub	1.00			6100.00		
Drill Pipe	29.50			6129.50		
Change Over Sub	1.00			6130.50		
Recorder	0.00	6751	Inside	6130.50		
Perforations	5.00			6135.50		
Recorder	0.00	6724	Outside	6135.50		
Bullnose	4.00			6139.50	42.50	Bottom Packers & Anchor
Total Tool Length:	**69.50**					

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22912 **DST#: 2**

Test Start: 2005.12.29 @ 11:00:26

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	52.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	5.99 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	2600.00 ppm				
Filter Cake:	inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
0.00	1000 GIP	0.000
30.00	10% gas, 90% Mud.	0.148


Total Length: 30.00 ft Total Volume: 0.148 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:

Laboratory Name: Laboratory Location:

Recovery Comments:


Pressure vs. Time
6751 Pressure
6751 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(2)
End Shut-In(1)
Open To Flow(1)
Shut-In(1)
Open To Flow(2)
Shut-In(2)
Pressure
Temperature
3000
2500
2000
1500
1000
500
0
130
120
110
100
90
80
70
60
50
40
12PM
3PM
6PM
9PM
Time (Hours)
29 Thu Dec 2005



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration Inc.**

9400 N. Broadway Ste. 400 Oklahoma City
Ok. 73114

ATTN: Ed Greaves

6/35/31

Deborah #1

Start Date: 2005.12.30 @ 10:15:36
End Date: 2005.12.30 @ 21:05:51
Job Ticket #: 22913 DST #: 3

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Raydon Exploration Inc.

9400 N. Broadw ay Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22913 **DST#: 3**

Test Start: 2005.12.30 @ 10:15:36

GENERAL INFORMATION:

Formation: **Upper Chester**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 13:14:51
Time Test Ended: 21:05:51

Test Type: Conventional Bottom Hole
Tester: Harley Davidson
Unit No: 33

Interval: 6170.00 ft (KB) To 6270.00 ft (KB) (TVD)
Total Depth: 6270.00 ft (KB) (TVD)
Hole Diameter: 7.78 inches Hole Condition: Poor


Reference Elevations: 2723.00 ft (KB)
2711.00 ft (CF)
KB to GR/CF: 12.00 ft

Serial #: 6751 **Inside**

Press@RunDepth: 33.08 psig @ 6236.00 ft (KB)
Start Date: 2005.12.30 End Date: 2005.12.30
Start Time: 10:15:37 End Time: 21:05:51

Capacity: 7000.00 psig
Last Calib.: 1899.12.30
Time On Btm: 2005.12.30 @ 13:10:36
Time Off Btm: 2005.12.30 @ 17:39:21

TEST COMMENT: IF- Weak building blow , 8" in bucket.
ISI- No blow back.
FF- Weak building blow , 5" into bucket.
FSI- No blow back.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2988.71	120.74	Initial Hydro-static
5	27.38	120.70	Open To Flow (1)
34	31.18	122.27	Shut-In(1)
97	141.26	125.03	End Shut-In(1)
98	20.00	124.96	Open To Flow (2)
159	33.08	126.97	Shut-In(2)
266	191.30	129.47	End Shut-In(2)
269	2918.83	132.13	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
0.00	1000' GIP	0.00
60.00	SGCM, TR gas, 100% mud.	0.30

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22913 **DST#: 3**

Test Start: 2005.12.30 @ 10:15:36

Tool Information

Drill Pipe:	Length:	5846.00 ft	Diameter:	3.80 inches	Volume:	82.00 bbl	Tool Weight:	1800.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length:	310.00 ft	Diameter:	2.25 inches	Volume:	1.52 bbl	Weight to Pull Loose:	110000.0 lb
					Total Volume:	83.52 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:		13.00 ft					String Weight: Initial	85000.00 lb
Depth to Top Packer:		6170.00 ft					Final	85000.00 lb
Depth to Bottom Packer:		ft						
Interval betw een Packers:		100.00 ft						
Tool Length:		127.00 ft						
Number of Packers:		2	Diameter:	6.75 inches				

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			6144.00		
Shut In Tool	5.00			6149.00		
Hydraulic tool	5.00			6154.00		
Jars	5.00			6159.00		
Safety Joint	2.00			6161.00		
Packer	5.00			6166.00	27.00	Bottom Of Top Packer
Packer	4.00			6170.00		
Stubb	1.00			6171.00		
Change Over Sub	1.00			6172.00		
Drill Pipe	62.00			6234.00		
Change Over Sub	1.00			6235.00		
Perforations	1.00			6236.00		
Recorder	0.00	6751	Inside	6236.00		
Perforations	30.00			6266.00		
Recorder	0.00	6724	Outside	6266.00		
Bullnose	4.00			6270.00	100.00	Bottom Packers & Anchor
Total Tool Length:	**127.00**					

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration Inc.

9400 N. Broadway Ste. 400 Oklahoma City Ok. 73114

ATTN: Ed Greaves

Deborah #1

6/35/31

Job Ticket: 22913 **DST#: 3**

Test Start: 2005.12.30 @ 10:15:36

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	52.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	6.99 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	2800.00 ppm				
Filter Cake:	inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
0.00	1000' GIP	0.000
60.00	SGCM, TR gas, 100% mud.	0.295

Total Length: 60.00 ft Total Volume: 0.295 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:

Laboratory Name: Laboratory Location:

Recovery Comments:


Pressure vs. Time
6751 Pressure
6751 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(1)
End Shut-In(2)
Open To Flow(1)
Shut-In(1)
Open To Flow(2)
Shut-In(2)
Pressure
Temperature
3000
2500
2000
1500
1000
500
-0
130
120
110
100
90
80
70
60
50
40
30
12PM
3PM
6PM
9PM
Time (Hours)
30 Fri Dec 2005