

WICHITA BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.


15-175-20359
12-35-31W

S. 12 T. 35 R. 31 ^NW

Loc. C NE SW

County Seward

640 Acres
N



Locate well correctly

Elev.: Gr. 2652'

DF _____ KB 2657'

API No. 15 — 175 — 20,359
County Number

Operator
B & B Farm Industries, Inc.

Address
P. O. Box 638 Spearman, Texas 79081

Well No. #1 Lease Name Larry

Footage Location
1980 feet from ~~XX~~ (S) line 1980 feet from ~~XX~~ (W) line

Principal Contractor Sage Drilling Geologist Joe Blair

Spud Date 4-17-78 Total Depth 6170' P.B.T.D. 6085'

Date Completed June 1, 1978 Oil Purchaser Wait on Pipe Line Connection

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1541'	Hall. lite Class "H"	650 sx 150 sx	2% CaCl 3% CaCl
Production	7-7/8"	4-1/2"	10.50#	6167'	Pozmix	525 sx	18% salt .75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					
TUBING RECORD			28 holes	DML	5992-6114'
Size	Setting depth	Packer set at			
2-3/8"	6055'	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
750 gal. 15% MCA - 12 RCN ball sealers	6089 - 6114'
2000 gal. 15% MCA - 25 RCN ball sealers	5992 - 6054'

INITIAL PRODUCTION

Date of first production June 18, 1978	Producing method (flowing, pumping, gas lift, etc.) Flow
RATE OF PRODUCTION PER 24 HOURS	Oil - bbls. Gas 230 MCF Water - bbls. Gas-oil ratio - CFPB
Disposition of gas (vented, used on lease or sold) Wait on Pipeline Connection	Producing interval(s) 5992 - 6054'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator B & B Farm Industries, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas

Well No.

1

Lease Name

Larry

S 12 T 35 R 31 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime, Silt and Shale	2976	3334	Council Grove	
Lime and Shale	3334	4450		
Lime and Shale	4450	4566	Toronto	
Lime and Shale	4566	5318	Lansing	
Lime and Shale	5318	5490	Marmaton	
Shale and Lime	5490	5848	Cherokee	
Shale and Lime	5848	5988	Morrow	
Lime and Shale	5988	6170 TD	Miss.	
<p>Welex Dual Induction G- Acous-Cal</p> <p>DST 5910-5994 no data available</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

R. W. Gignilotta

Signature

Petroleum Engineer

Title

April 16, 1979

Date