


Company- J. M. HUBER CORP.  
 Farm- Blucher No. 1

SEC. 13 T. 35 R. 31W  
 CSW NE

Total Depth. 6350  
 Corum. 8-11-53 Comp. 9-19-53  
 Shot or Treated.  
 Contractor. The R. W. Rine Drlg. Co.  
 Issued. 1-23-54

County Seward  
 KANSAS



Elevation. 2679

Production. Dry

CASING:

13 3/8" 638' cem. w/500 sx  
 9 5/8" 2405' cem. w/375 sx

Figures indicate Bottom of Formation

surface sand	75
clay, shale & shells	590
red bed	650
red bed & shale	1340
red bed, shale & shells	1475
shale	1650
shale & salt	1795
shale & shells	1935
shale & sand	2055
shells, shale & lime	2225
shale, sand & lime	2358
shale, lime strata & anhydrite	2405
shale & lime	2490
sandy lime & shale	2625
shale, lime & salt	2685
lime & shale	2895
lime	2965
lime & shale	3406
chalk lime & shale	3450
lime & shale	3825
lime	3845
shale & lime	4520
lime hard	4575
lime & shale	4731
lime, shale & chert	4790
lime	4955
lime & chert	5050
lime	5055
cherty lime & shale	5140
lime & shale	5254
lime hard	5290
lime & shale	5440
cherty lime & shale	5501
lime	5537
lime & shale	5658
shale	5715
shale & lime	6160
lime	6230
lime & shale	6350
Total Depth	

Tops:	
Lansing	4488
Morrow	5926
Mississippi	6140