

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2 - 35 - 33W ✓

Company- PAN AMERICAN PETROLEUM CORP.
Farm- Feldman Gas Unit No. 1

SEC. 2 T. 35 R. 33W
C SW NE

Total Depth. 6450'
Comm. 8-3-62 Comp. 8-28-62
Shot or Treated.
Contractor. Lynn Drilling
Issued. 3-23-63

County Seward
KANSAS



CASING:
8 5/8" 1608' cem w/1200 sx.

Elevation. 2815' DF

Production. DRY

Figures indicate Bottom of Formations.

surface sand-clay	109
sand	585
red bed	923
sand	1598
anhydrite	1759
gyp-anhydrite-shale	2532
shale-sand	2680
shale-sand-lime	2920
shale-lime	3097
shale-lime-sand	3208
lime-shale	3351
shale-sand-chalk	3665
shale-lime	3787
shale-lime-chalk	3923
shale-lime	4752
lime	4787
shale-lime	5450
lime	5560
shale-lime	5606
shale	5856
shale-lime	5989
shale	6021
shale-sand	6189
shale-lime	6280
shale	6303
shale-lime	6450
Total Depth	
TOPS: SAMPLE	
Anhydrite	1562
TOPS: LOG	
Chase	2632
Toronto	4400
Lansing	4538
Des Moines	5264
Morrow	5864
Morrow Sand	6070
Chester	6130
Chester Sand	6407