

14-35-33W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. STANOLIND OIL AND GAS COMPANY
Farm. Ray Matkin No. 1

SEC. 14 T. 35 R. 33W
SW NE NE
990' SN1 & 990' WE1 NE $\frac{1}{4}$

Total Depth. 6238' PB 6134'
Comm. 5-28-47 Comp. 7-26-47
Shot or Treated.
Contractor.
Issued. 10-18-47

County. Soward
KANSAS



CASING:

13-3/8" 663' Com. w/700 sx
8-5/8" 2432' Com. w/500 sx

Elevation. 2802' *at*

Production. Est. 55 bbls
distillate per day

		Figures Indicate Bottom of Formations.			
sand & gravel	0-225	lime sandy	5153	Tops:	
sand	560	lime & shalo	5192	Lansing	4370
sand & shale	600	limo blk & gy	5199	Mississippi	6143
red rock	670	limo	5237		
red bed & sand	1225	limo cherty	5271		
sand & shale	1490	limo hrd & shalo	5285		
shalo w shells	1822	limo & chert	5299		
anhydrite	1835	limo w shalo	5316		
shalo & shells	1868	limo	5407		
shale, shells & strks/any.	1933	limo & shalo	5505		
shalo & shells	2102	limo	5567		
anhydrite & shalo	2286	shalo & limo			
red bed, shale & shells	2355	shells	5617		
anhydrite & shale	2455	limo & shalo	5657		
sand, shale & shells	2493	shalo	5791		
shalo w anhydrite	2584	shalo & limo	5984		
anhydrite w shalo, brkn limo		shalo	6069		
shells & dolomite	2628	sand	6105		
anhydrite w shalo	2720	Core #1 6105-12 Rec.			
anhydrite brkn, lime & shale	2758	1' sand, slight odor			
shalo & limo	3111	Core #2 6112-15 Rec.			
limo	3162	1' sand, slight odor			
lime gy	3240	Core #3 6115-24 Rec.			
lime	3325	9' gy coarse sand w/sli. odor			
shalo & limo	3395	Core #4 6124-32 Rec. 8'			
lime w shale strks	3467	3' sand			
shalo & lime	3504	5' poker chip shalo			
shale gummy & lime shells	3540	Core #5 6137-54 Rec. 15'			
lime chalky & shells	3546	3' lime			
lime brkn	3627	2' sh			
lime & shalo	3712	5' limo			
lime brkn, shale & sand	3746	1' shaley limo			
lime brkn	3820	4' limo			
shale, lime shells & sand	3861	Core #6 6154-66 Rec. 12'			
limo & shale	3942	5' blk green poker chip shalo			
shale	4015	7' blk brwn tight lime			
shale & lime	4378	Core #7 6166-84 Rec. 16'			
limo	4420	4' shalo			
limo w shalo	4455	12' hrd tight limo			
lime brkn & shalo	4521	Core #8 6184-6202 Rec.			
limo & shalo	4526	4' limoy shalo			
limo	4541	Core #9 6202-20 Rec. 8'			
limo w shalo	4565	7' brwn oolitic tight lime			
lime & shalo brkn	4581	1' brwn crinoidal tight lime			
limo	4606	no show, no porosity			
lime & shalo	4657	Core #10 6220-38 Rec. 11'			
shalo blue	4685	2' oolitic lime			
limo w shalo	4708	4' blk dense shaley & dolomitic			
shalo, limo & chert	4727	lime			
chert blk & shale	4749	5' brwn tight foss. lime			
lime blk & limo	4787	Total Depth	6238		
lime	4930				
limo & shale	4978	Plugged back to 6134'			
limo	5001				
lime & sand	5049				