


12-35-34W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. PANHANDLE EASTERN PIPE LINE CO.  
Farm. Dunlap No. 1

SEC. 12 T. 35 R. 34W  
NE NW SE NW  
1600' S of NL,  
1700' E of WL, NW $\frac{1}{4}$   
County Seward  
KANSAS

Total Depth. 2752  
Comm. 12-11-52 Comp. 1-15-53  
Shot or Treated.  
Contractor. Walter Kuhn Drilling Co.  
Issued. 6-20-53



CASING:  
10 3/4 719' w/ 325 sx cement  
6 5/8 2645' w/ 150 sx cement

Elevation. 2887.3

Production. 7,000,000 gas

Figures Indicate Bottom of Formations.

clay & sand	190
sand & shells	380
clay & sand	640
red bed	800
red sand & shells	930
gyp	975
red bed & sand	1300
red bed & shells	1550
broken anhydrite	1585
anhydrite	1830
broken anhydrite, red rock & shale	2000
broken anhydrite & shale streaks	2150
anhydrite	2208
broken anhydrite & shale	2285
anhydrite	2610
anhydrite & lime	2651 RTD
lime	2752
Total Depth	

TOPS:	
Hollenberg	2586
Herrington	2635
Upper Krider	2696
Lower Krider	2734

GAS LOG:  
Small show 2750-51 OF too small to gauge

Acidized:  
1-13 3000 gals 15% 4100 gals wtr.  
well tested 400 MCF  
1-14 2000 gals 7 1/2% 4100 gals wtr.  
well tested 464 MCF  
1-15-5000 gals 15% 4200 gals wtr.  
Used 9000 gals. 15% acid  
OF after acid: none  
RP after acid: none