

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

10 - 35 - 34 W

Company- PANHANDLE EASTERN PIPE LINE COMPANY

Farm- Grover

No. 1

SEC. 10 T. 35 R. 34W

SW SW SW NW

2500' S of NL & 250' E of WL

NW/4

County Seward

KANSAS

Total Depth. 2746; PB 2740
 Comm. 12-3-51 Comp. 12-26-51
 Shot or Treated.

Contractor. W. Kuhn Drlg. Co.

Issued. 3-8-52

CASING:

10 3/4" 718' cem. w/275 sx, circ.
 7" 2634' cem. w/150 sx.
 2 3/8" tubing 2707', 33' Off Bottom.

Elevation. 2909.09

2908 (2nd)

Production. Est. 8,003,000 gas

Figures indicate Bottom of Formations.

sand & clay	400
clay & shale	610
sandy redbed	675
redbed	845
redrock & Anhydrite	1130
gyp, redbed, sand	1553
redbed, redsand	1600
Anhydrite	1760
Anhydrite & shale	1985
Anhydrite	2060
shale & Anhydrite	2238
Anhydrite	2280
Anhydrite & shale	2350
shale & lime	2472
lime, shale, Anhydrite	2525
lime & Anhydrite	2567
chert & Anhydrite	2587
Anhydrite & shale	2615
lime & Anhydrite	2645, RTD
lime	2744
shale	2746
Total depth; PB 2740	

Tops:

Hollinberg	2580
Herrington	2640
Krider	2659

Acid Record:

Acidized 12-22-52 with 3000 gals.
 15% acid and 4635 gals. water. No
 test taken after treatment.

Acidized 12-23-51 with 1000 gals.
 15% acid and 4635 gals. water.
 After blow 24 hrs. well tested
 656 MCF.

Acidized 12-27-51 with 6000 gals.
 15% acid and 4058 gals. water.
 After blowing 12 hrs. well tested
 2780 MCF.

Acidized 2-1-52, 10,000 gals. 15%
 acid and 6000 gals. water

Gas Log:

First show 2708' open flow to mall to
 gauge

Increase 2728, open flow 803 MCF

Original open flow: None taken

Original rock pressure: None taken

open flow after acid: None taken

Rock pressure after acid: None taken

Source: Driller Reports